

MICHAEL J. LAMOREAUX, P.E. (NY, NJ, PA, VT, VA & CT) MICHAEL W. WEEKS, P.E. (NY, NJ & PA) LYLE R. SHUTE, P.E., LEED-AP (NY, NJ, PA) PATRICK J. HINES Main Office 33 Airport Center Drive Suite 202 New Windsor, New York 12553

(845) 567-3100 fax: (845) 567-3232

e-mail: mheny@mhepc.com

Principal Emeritus:

RICHARD D. McGOEY, P.E. (NY & PA)

TOWN OF NEWBURGH PLANNING BOARD TECHNICAL REVIEW COMMENTS

PROJECT: FARRELL INDUSTRIAL PARK

PROJECT NO.: 20-16

PROJECT LOCATION: SECTION 1, BLOCK 1, LOT 63.23

REVIEW DATE: 12 FEBRUARY 2021 MEETING DATE: 18 FEBRUARY 2021

PROJECT REPRESENTATIVE: JMC ENGINEERING/JOSEPH P. MCDAFFERI

- 1. The Planning Board circulated its Notice of Intent for Lead Agency on 26 January 2021. The time frame for Lead Agency determination will not have been lapsed by the 18 February 2021 Planning Board meeting.
- 2. The Town Board is working with other projects in the vicinity of this project to evaluate fair share cost contributions to potential improvements at the Gardnertown Road/Route 300 intersection. Coordination between this project's Traffic Consultant and the NYSDOT as well as the Planning Board are required.
- **3.** The previously proposed emergency access drive has been removed from the latest set of plans. Comments from the Town's Code Department as well as Jurisdictional Fire Departments should be received regarding the single point of access to a facility of this size.
- **4.** The intent of previous comment #12 was to identify if blasting for the proposed project will be required.
- **5.** The project will require approval for the subsurface sanitary sewer disposal system from the NYSDEC and Orange County Health Department.
- **6.** The Applicants have provided further information regarding the Berry Lane right-of-way which extends through the site. It is unclear if the right-of-way is in favor of any entity. It is requested the Applicant consult with the Planning Board Attorney regarding the existence of the right-of-way and any impacts on the project.
- **7.** Potable water and fire service water to the structures must be designed in such a manner that if fire flow water is terminated, potable water to the structure is similarly terminated. Separate
 - Regional Office 111 Wheatfield Drive Suite 1 Milford, Pennsylvania 18337 570-296-2765 •



fire and potable water lines are currently proposed entering the buildings.

- **8.** A response from OPHRP has been received requesting additional information regarding cultural resources. The Applicants have retained the services of a cultural resources expert. Copies of this report should be submitted to the Planning Board for the SEQRA record.
- **9.** Previous comment #23 identified a fairly large survey "gore" on the northeast portion of the project. The Applicants response states additional information will be provided.
- **10.** The Applicants representative have identified that the proposed office portion of the warehouse had been noted as approximate, with the maximum area not to exceed 15% or the overall warehouse square footage. Currently the two story offices are identified at 18,500 and 10,500 square feet for buildings A & B respectively.
- **11.** Note #25 on Sheet C-310 should identify the submission of a stamped As-Built plans for the subsurface sanitary sewer disposal system be provided to Code Enforcement in addition to the required certification.
- **12.** Stormwater Pollution Prevention Plan comments will be sent under separate cover.
- **13.** Standard Town of Newburgh water and sewer notes must be added to the plans.
- **14.** The Applicants are requested to confirm that the Grading Plan for the site is a balanced Grading Plan or identify the amount of cut and fill material to be brought into or removed from the site.

Respectfully submitted,

McGoey, Hauser and Edsall Consulting Engineers, D.P.C.

Patrick J. Hines

Principal

PJH/kbw



Site Planning
Civil Engineering
Landscape Architecture
Land Surveying
Transportation Engineering

Environmental Studies Entitlements Construction Services 3D Visualization Laser Scanning

Farrell Industrial Park
Route 300
Town of Newburgh, NY
JMC Project 18156
Town of Newburgh Project No. 2020-16

Project Narrative

December 3, 2020 Revised: December 21, 2020

The subject property is located on the east side of Route 300, just north east of the Route 300 and Little Brook Lane (private road) intersection, or opposite The Storage Stop self-storage facility. In addition to having frontage on NYS Route 300, the property can be accessed via an existing driveway from Berry Lane along the northerly property line. The property presently consists of an abandoned 2-story wood frame dwelling, remnants of a wood frame shed, and some pathways, but us otherwise undeveloped. To the best of our knowledge, the property does not have a street address, but is identified by the Town of Newburgh Tax Designation of Section 34, Block 2, Lot 45. It is within the IB Interchange Business Zoning District and abuts the R1 Single Family Residence Zoning District to the north.

Farrell Building Company is proposing to construct an Industrial Park development on the property which would consist of two warehouse buildings totaling 290,000 SF (Building A will be 185,000 SF and Building B will be 105,000 SF) and the associated site improvements. The site improvements will include but not be limited to a site access drive from Route 300, an emergency access drive from Berry Lane (gated at the property line and site access drive), 251 parking spaces, 72 loading spaces, 40 truck/trailer parking spaces, stormwater management systems, a private watermain extension, a septic system, landscaping, and lighting.

The onsite wetlands were determined to be under the jurisdiction of the Army Corps of Engineers (USACE) and delineated accordingly by Ecological Solutions, LLC on March 26, 2019. The delineation was followed by the preparation of a "Wetland Delineation Report", also prepared by Ecological Solutions, LLC, and dated September 21, 2020. The USACE does not have a buffer requirement. These wetlands were mapped by the project surveyor and are shown on the site plans for information and reference. There is no wetland disturbance proposed as part of this project.

Municipal water is available to the site via a 16" watermain in Route 300, which will be tapped for domestic and fire service. The service will be considered a private watermain extension and subject to the review/approval of the Orange County Department of Health. Municipal sewer is not available to the site. Therefore, construction of a septic system will be required to serve the project. The design of this system will also be subject to the review/approval of the Orange County Department of Health.

JMC Planning Engineering Landscape Architecture & Land Surveying, PLLC | JMC Site Development Consultants, LLC

Since the end user of the site has yet to be determined and many design/operational aspects of the project are based upon the number of employees, the number of employees were determined based upon publications by the Energy Star division of the United Stated Department of Environmental Protection (EPA) entitled "Warehouse Space Use Information", "Warehouse Data Trends", and "Distribution Center Data Trends". These publications are prepared based upon data from actual warehouse and distribution center operators that is input to the EPA's Energy Star Portfolio Manager – an online tool to measure and track energy and water usage. These publications provide information regarding the occupant density for the total number of employees in a warehouse and distribution center uses, with an average at 0.5 employees/1,000 SF and a 95th percentile at 1.5 employees/1,000 SF. This project has conservatively accounted for 1 employee/1,000 SF.

As noted above, the northerly boundary of the property abuts the RI – Single Family Residence District. Therefore, a 100-foot landscape buffer is required and has been incorporated into the design. Abutting the residential district also increases that side yard setback to 228 feet, which the project complies with.

As you are aware, the Town Code defines building height as "the vertical distance measured from the average elevation of the finished grade along the side of the structure facing the street to the highest point of such structure." Based upon this definition and when considering the proposed grades, the height of Buildings A and B are 45.8 and 48.8 feet respectively, where 40 feet is the maximum permitted. Accordingly, a variance is anticipated to be required. The actual height of both buildings from the finished floor to the top of the 3-foot parapet will be 45 feet. The 42-foot roof elevation is proposed in an effort to provide the preferred interior ceiling height of 38 feet, which is an industry standard. Building A will have some minor adjustments to the grade within the emergency access drive at both ends of the structure in order to meet grades at the truck parking area to the south and the site access drive to the north, which is the reason for the slight increase in the calculated building height (average grade is used). The increase in the height for Building B, based upon average grade along the façade facing the street, is due to the need for the grade outside the loading docks to be 4 feet below the finished floor. It is important to note the following regarding the building height:

- A. The finished floor of each building is the same elevation.
- B. Building A will completely screen loading docks of Building B from the street.
- C. Both buildings are several hundred feet from the roadway and are tucked behind other parcels that have frontage on the street.
- D. All loading docks are situated to be internal to the site and are not oriented out towards the property perimeter.

Based upon the above, both buildings will appear to be the same height when viewed from the property perimeter.

The above noted "Wetland Delineation Report" and EPA "Data Trend" publications are attached to this Narrative for information and reference.

Connecticut 1248 Southford Road Southbury, CT 06488 Phone (203) 910-4716 ecolsol@aol.com

September 21, 2020

Joseph Modafferri, Jr., RLA c/o JMC 120 Bedford Road Armonk, NY 10504

> Re: Wetland Delineation Yune Site - Route 300 Town of Newburgh, Orange County, New York

Dear Joe:

Ecological Solutions, LLC completed a wetland delineation on March 26, 2019 at the site located on Route 300 in the Town of Newburgh, Orange County, New York (*Figure 1*). The delineation was completed in accordance with the Army Corps of Engineers (USACE) Wetlands Delineation Manual (January 1987), Routine Determination Method and Northcentral/Northeast supplement. There is no New York State Department of Environmental Conservation (NYSDEC) regulated wetland at this location.

Federal wetlands were delineated based upon the identification of the three mandatory criteria for wetland determination as outlined in the 1987 Federal Manual and supplement: dominant hydrophytic vegetation, hydric soils, and evidence of wetland hydrology. The Routine Methodology procedure for wetland determination was used. Transects consisting of at several sample points were walked. Dominant vegetation around each sample point was identified and its percent cover quantified. The areas were checked in detail for the presence of wetland hydrologic indicators. Soil profiles were then observed and characterized at each point.

The detailed field investigation included:

- 1. Identification of vegetation species to determine whether there was a dominance of hydrophytic plants and areas containing transitional but primarily wetland-oriented species.
- 2. Determination of soil features for hydric (poorly and very poorly drained) natural soils.
- 3. Observation of site features displaying evidence of wetland hydrology based on the presence of inundated areas, apparent high seasonal water tables, and evidence of saturation within 12 inches of the surface (considered the root zone) during sufficient periods during the growing season to provide for anaerobic/hydric soil conditions.

Based on observed field conditions a federal wetland was delineated on the eastern section of the site and is regulated by the USACE as "waters of the US". There is no regulatory buffer attached to the wetland. The wetland boundary is shown on the map entitled, "Topographic Survey of Property State Highway Route 300" prepared by JMC and dated 5/23/2019 and last revised 07/11/2019.

If you need any additional information, please contact me.

Sincerely,


ECOLOGICAL SOLUTIONS, LLC

Milul Minhe

Michael Nowicki

Biologist

Figure 1 Location Map






Energy Use in Non-Refrigerated Warehouses




The U.S. Environmental Protection Agency's (EPA) ENERGY STAR Portfolio Manager is changing the way organizations track and manage energy. Because of this widespread market adoption, EPA has prepared the DataTrends series to examine benchmarking and trends in energy and water consumption in Portfolio Manager. To learn more, visit www.energystar.gov/DataTrends.

What is a typical operating profile?

Energy use intensity (EUI) ranges from less than 50 to more than 600 kBtu/ft² across all non-refrigerated warehouses, with those at the 95th percentile using nearly 21 times the energy of those at the 5th percentile. The distribution has a negative skew, which means the most energy intensive properties are further away from the median than the most efficient. Properties may use more or less energy for many reasons, including variable equipment efficiency and energy management practices, as well as variations in climate and business activities.



The median non-refrigerated warehouse in Portfolio Manager is approximately 36,000 square feet and operates 55 hours per week. But the typical property use patterns observed in Portfolio Manager vary just as much as energy. As you can see, there are non-refrigerated warehouses of all shapes and sizes benchmarking in Portfolio Manager.




Benchmarking by State

		Range of Values		
	Property Characteristic	5th percentile	Median	95th percentile
	Square Feet	7,245	36,316	337,740
<u>OPEN</u>	Weekly Operating Hours	40	55	141
	Workers per 1,000 ft ²	0.1	0.6	1.9
	Walk-in Refrigerators?	3	3% say yes	;
	Heating Degree Days	911	4,483	7,854
ශී	Cooling Degree Days	124	1,056	3,285

What is Source Energy? Source energy is the amount of raw fuel required to operate your property. In addition to what you use on site, source energy includes losses from generation, transmission, and distribution of energy. Source energy enables the most complete and equitable energy assessment. Learn more at: www.energystar.gov/SourceEnergy.

What characteristics affect energy use in non-refrigerated warehouses?


Business activity and climate are often correlated with energy consumption. For example, non-refrigerated warehouses that have more workers per square foot, operate more hours and/or experience more heating degree days (HDD) use more energy, on average. The orange trend lines in the graphs below are steeper for workers and operating hours, meaning that these characteristics have a stronger effect on energy than HDD. While these trends hold true on average, two properties with the same number of workers could have very different energy use, as shown by the range in the blue dots. Trends can also be seen for other indicators of business activity, such as number of walk-in refrigerators and cooling degree days.




Heating Degree Days

How does EPA's ENERGY STAR score vary with energy use?

EPA's ENERGY STAR score normalizes for the effects of operation. While properties with lower EUI generally earn higher scores on the 1-100 scale, an individual property's result depends on its business activities. For any given EUI, a range of scores is possible.



Let's look at two non-refrigerated warehouses, Warehouse A and Warehouse B. They have the same EUI of 107 kBtu per square foot, and are identical except that Warehouse B has more workers per square foot and operates for more hours per week. Because Warehouse B has more intensive activities, it is expected to have a higher EUI than Warehouse A, based on ENERGY STAR scoring models. Since Warehouse B is expected to use more energy, but actually uses the same energy, it earns a higher score.



Total number and floor area of properties benchmarked reflects cumulative data through 2013. Analysis of energy use and operational characteristics includes 5,203 properties benchmarked in the most recent 5 Because of small sample size, refrigerated warehouses were excluded from this data sheet. The data is self reported and has been filtered to exclude outliers, incomplete records, and test facilities. Portfolio Manager is not a randomly selected sample and is not the basis of the STAR score. To learn www.energystar.gov/DataTrends.





Energy Use in Distribution Centers

Distribution Centers Using Portfolio Manager

1,835 Properties



485 Million ft²



Average

ENERGY STAR Score

The U.S. Environmental Protection Agency's (EPA) ENERGY STAR Portfolio Manager is changing the way organizations track and manage energy. Because of this widespread market adoption, EPA has prepared the DataTrends series to examine benchmarking and trends in energy and water consumption in Portfolio Manager. To learn more, visit www.energystar.gov/DataTrends.


Property

Benchmarking by State

Number of Distribution Centers

What is a typical operating profile?

Energy use intensity (EUI) ranges from less than 50 to more than 600 kBtu/ft² across all distribution centers, with those at the 95th percentile using 16 times the energy of those at the 5th percentile. The distribution has a negative skew, which means the most energy intensive properties are further away from the median than the most efficient. Properties may use more or less energy for many reasons, including variable equipment efficiency and energy management practices, as well as variations in climate and business activities.



The median distribution center in Portfolio Manager is approximately 110,000 square feet and operates 60 hours per week. But the typical property use patterns observed in Portfolio Manager vary just as much as energy. As you can see, there are distribution centers of all shapes and sizes benchmarking in Portfolio Manager.

Up to 5 6 - 10 11 - 25 26 - 50 More than 50


Range of Values

	Characteristic	percentile	Median	percentile
	Square Feet	9,992	110,431	887,014
OPEN	Weekly Operating Hours	40	60	168
	Workers per 1,000 ft ²	0.1	0.4	1.5
	Walk-in Refrigerators?	(9% say yes	\$
	Heating Degree Days	864	4,401	7,162
S	Cooling Degree Days	171	1,136	3,208

What is Source Energy? Source energy is the amount of raw fuel required to operate your property. In addition to what you use on site, source energy includes losses from generation, transmission, and distribution of energy. Source energy enables the most complete and equitable energy assessment. Learn more at: www.energystar.gov/SourceEnergy.


What characteristics affect energy use in distribution centers?

Business activity and climate are often correlated with energy consumption. For example, distribution centers that have more workers per square foot, operate more hours and/or have more heading degree days (HDD), on average. The orange trend line in the graphs below is the steepest for workers meaning that worker density has stronger effect on energy than hours or HDD. While these trends hold true on average, two properties with the same number of workers could have very different energy use, as shown by the range in the blue dots. Trends can also be seen for other indicators of business activity, such as number of walk-in refrigerators.




How does EPA's ENERGY STAR score vary with energy use?

EPA's ENERGY STAR score normalizes for the effects of operation. While properties with lower EUI generally earn higher scores on the 1-100 scale, an individual property's result depends on its business activities. For any given EUI, a range of scores is possible.



Let's look at two distribution centers, Center A and Center B. They have the same EUI of 109 kBtu per square foot, and are identical except that Center B has more workers per square foot and operates for more hours per week. Because Center B has more intensive activities, it is expected to have a higher EUI than Center A, based on ENERGY STAR scoring models. Since Center B is *expected* to use more energy, but *actually* uses the same energy, it earns a higher score.



number and floor area Total of properties benchmarked reflects cumulative data through 2013. Analysis of energy use and property characteristics includes 1,554 properties benchmarked in the most recent 5 years. data is self reported and has been filtered to exclude outliers, incomplete records, and test facilities. Portfolio Manager is not a randomly selected sample and is not the basis of the **ENERGY** STAR score. To learn www.energystar.gov/DataTrends.



Full Environmental Assessment Form Part 1 - Project and Setting

Instructions for Completing Part 1

Part 1 is to be completed by the applicant or project sponsor. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification.

Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information; indicate whether missing information does not exist, or is not reasonably available to the sponsor; and, when possible, generally describe work or studies which would be necessary to update or fully develop that information.

Applicants/sponsors must complete all items in Sections A & B. In Sections C, D & E, most items contain an initial question that must be answered either "Yes" or "No". If the answer to the initial question is "Yes", complete the sub-questions that follow. If the answer to the initial question is "No", proceed to the next question. Section F allows the project sponsor to identify and attach any additional information. Section G requires the name and signature of the applicant or project sponsor to verify that the information contained in Part 1 is accurate and complete.

A. Project and Applicant/Sponsor Information.

Project Location (describe, and attach a general location map):				
NYS Route 300 (Plattekill Turnpike), Town of Newburgh, NY				
Brief Description of Proposed Action (include purpose or need): The Applicant proposes the construction of two warehouse buildings on the Site. One is proposed to be 185,000 square feet and the other 105,000 square feet, with a total of 290 employees. The site improvements include a single access driveway off of NY Route 300, as well as parking for cars and loading spaces for trucks. The height of the proposed buildings is 45 feet to the top of the parapet and 49 feet from the average finished grade, where a maximum of 40 feet is permitted. The project will therefore require a building height variance. See Project Narrative for further discussion.				
Telephone: 631-766-0023				
f Applicant/Sponsor: uilding Company phen Zagoren Telephone: 631-766-0023 E-Mail: zags1413@gmail.com				
State: NY	Zip Code: 11932			
Telephone: 914-273-5225				
JMC Planning Engineering Landscape Architecture & Land Surveying, PLLC Attn.: Joseph P. Modafferi, Jr., RLA				
State: NY	Zip Code: 10504			
Telephone:				
E-Mail:				
State: NY	Zip Code: 10512			
	Telephone: 631-766-0023 E-Mail: zags1413@gmail.com State: NY Telephone: 914-273-5225 E-Mail: jmodafferi@jmcpllc.com State: NY Telephone: E-Mail: pmodafferi@jmcpllc.com			

B. Government Approvals

B. Government Approvals, Funding, or Sponassistance.)	sorship. ("Funding" includes grants, loans, ta	ix relief, and any other	forms of financial	
Government Entity	If Yes: Identify Agency and Approval(s) Required	Application (Actual or p		
a. City Counsel, Town Board, ☐Yes ✓ No or Village Board of Trustees				
b. City, Town or Village ✓ Yes No Planning Board or Commission	Site Plan Approval	12/04/2020		
c. City, Town or ✓ Yes No Village Zoning Board of Appeals	Building Height variance	01/14/2021		
d. Other local agencies				
e. County agencies ✓ Yes No	Health Dept. septic system approval; private watermain ext. Orange County §239-m General Municipal Law Referral	TBD		
f. Regional agencies				
g. State agencies Yes No	NYSDEC SPDES General Permit GP-0-20-001 NYSDOT Highway Work Permit	TBD		
h. Federal agencies				
i. Coastal Resources.i. Is the project site within a Coastal Area, or	or the waterfront area of a Designated Inland W	/aterway?	∐Yes √No	
 ii. Is the project site located in a community with an approved Local Waterfront Revitalization Program? iii. Is the project site within a Coastal Erosion Hazard Area? 				
C. Planning and Zoning				
C.1. Planning and zoning actions.				
Will administrative or legislative adoption, or a only approval(s) which must be granted to ena If Yes, complete sections C, F and G. If No, proceed to question C.2 and con	mendment of a plan, local law, ordinance, rule ble the proposed action to proceed? nplete all remaining sections and questions in		∏Yes ✓ No	
C.2. Adopted land use plans.				
a. Do any municipally- adopted (city, town, vi where the proposed action would be located	llage or county) comprehensive land use plan(s) include the site	✓Yes No	
If Yes, does the comprehensive plan include sp would be located?	ecific recommendations for the site where the	proposed action	∐Yes √ No	
b. Is the site of the proposed action within any local or regional special planning district (for example: Greenway; Brownfield Opportunity Area (BOA); designated State or Federal heritage area; watershed management plan; or other?) If Yes, identify the plan(s): □ Yes ✓ No				
c. Is the proposed action located wholly or par or an adopted municipal farmland protection	tially within an area listed in an adopted munic	ipal open space plan,	Yes / No	
If Yes, identify the plan(s):	If Yes, identify the plan(s):			

C.3. Zoning	
 a. Is the site of the proposed action located in a municipality with an adopted zoning law or ordinance. If Yes, what is the zoning classification(s) including any applicable overlay district? IB "Interchange Business" 	✓ Yes No
b. Is the use permitted or allowed by a special or conditional use permit?	✓ Yes No
c. Is a zoning change requested as part of the proposed action? If Yes, i. What is the proposed new zoning for the site?	☐ Yes ✓ No
C.4. Existing community services.	
a. In what school district is the project site located? Newburgh Central School District	
b. What police or other public protection forces serve the project site? Town of Newburgh Police Department	
c. Which fire protection and emergency medical services serve the project site? Cronomer Valley Fire District; Town of Newburgh Emergency Medical Services	<u> </u>
d. What parks serve the project site? Chadwick Lake Park; Cronomer Hill Park; Algonquin Park	
D. Project Details	
D.1. Proposed and Potential Development	
a. What is the general nature of the proposed action (e.g., residential, industrial, commercial, recreational; if mixed components)? Commercial, residential	l, include all
b. a. Total acreage of the site of the proposed action? b. Total acreage to be physically disturbed? c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor? ±35.21 acres ±35.21 acres	
c. Is the proposed action an expansion of an existing project or use? i. If Yes, what is the approximate percentage of the proposed expansion and identify the units (e.g., acres, miles square feet)? % Units:	☐ Yes ✓ No , housing units,
 d. Is the proposed action a subdivision, or does it include a subdivision? If Yes, i. Purpose or type of subdivision? (e.g., residential, industrial, commercial; if mixed, specify types) 	∏Yes √ No
ii. Is a cluster/conservation layout proposed?iii. Number of lots proposed?	∐Yes ∏No
e. Will the proposed action be constructed in multiple phases? i. If No, anticipated period of construction: ii. If Yes: • Total number of phases anticipated • Anticipated commencement date of phase 1 (including demolition) • Anticipated completion date of final phase • Generally describe connections or relationships among phases, including any contingencies where progred determine timing or duration of future phases:	Yes No

f. Dans the emain	et in aluda navy ragid	ontial uses?			Yes No
	et include new resid abers of units propo-				_ ·
ii res, snow nun	One Family	Two Family	Three Family	Multiple Family (four or more)	
	One I anniy	1 WO 1 daining	<u> </u>		
Initial Phase		V		-	
At completion					
of all phases	\ 			-	
g. Does the prope	sed action include	new non-residenti	al construction (inclu	iding expansions)?	√Yes No
If Yes,					
i. Total number	of structures 2		40		
ii. Dimensions (in feet) of largest p	roposed structure:	49 height;	250 width; and	
iii. Approximate	extent of building	space to be heated	or cooled:	square feet	
h. Does the prope	sed action include	construction or ot	her activities that wil	l result in the impoundment of any	☐Yes ✓ No
liquids, such a	s creation of a wate	r supply, reservoir	r, pond, lake, waste l	agoon or other storage?	
If Yes,					
i. Purpose of the	e impoundment:			70 1 / FG Committee at 1999	Other specific
ii. If a water imp	oundment, the prin	cipal source of the	e water:	Ground water Surface water stream	nsOther specify:
iii If other then	voter identify the t	me of impounded	/contained liquids an	d their source	
iv. Approximate	size of the propose	d impoundment.	Volume:	million gallons; surface area:height;length	acres
v. Dimensions of	of the proposed dam	or impounding st	ructure:	height;length	
vi. Construction	method/materials 1	for the proposed d	am or impounding st	ructure (e.g., earth fill, rock, wood, cond	crete):
D.2. Project Op					
a. Does the propo	osed action include	any excavation, m	nining, or dredging, d	uring construction, operations, or both?	☐Yes ✓ No
(Not including	general site prepara	ation, grading or i	nstallation of utilities	or foundations where all excavated	
materials will	remain onsite)				
If Yes:					
i. What is the p	urpose of the excava	ation or dredging?		1 1.0 4114-0	
ii. How much ma	iterial (including ro	ck, earth, sedimen	its, etc.) is proposed t	to be removed from the site?	
• Over w	hat duration of time	?	ha avanuated or drad	ged, and plans to use, manage or dispos	e of them
iii. Describe nati	ire and characteristi	es of materials to	be excavated of died	ged, and plans to use, manage or dispos	c of thom.
-					
iv. Will there be	e onsite dewatering	or processing of e	excavated materials?		Yes No
If yes, descr					
v. What is the t	otal area to be dredg	ged or excavated?		acres	
vi. What is the r	naximum area to be	worked at any on	e time?	acres	
vii. What would	be the maximum de	epth of excavation	or dredging?	feet	
viii. Will the exc	avation require blas	sting?			☐Yes ☐No
ix. Summarize si	te reclamation goal	s and plan:			
b. Would the pro	posed action cause	or result in alterat	tion of, increase or de	ecrease in size of, or encroachment	☐ Yes ✓ No
	ing wetland, waterb	oody, shoreline, be	each or adjacent area	<i>!</i>	
If Yes:	4 1 4 1 -	1	a affacted (he mans	water index number, wetland map numb	ner or geographic
					or or Poograpine
description):					
·					

ii. Describe how the proposed action would affect that waterbody or wetland, e.g. excavation, fill, placemen	t of structures, or
alteration of channels, banks and shorelines. Indicate extent of activities, alterations and additions in squa	re reet or acres:
iii. Will the proposed action cause or result in disturbance to bottom sediments?	☐Yes ☐No
If Vac describe:	
iv. Will the proposed action cause or result in the destruction or removal of aquatic vegetation?	☐ Yes ☐ No
If Yes:	
acres of aquatic vegetation proposed to be removed:	
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
• purpose of proposed removal (e.g. beach clearing, invasive species control, boat access):	
proposed method of plant removal:	
• if chemical/herbicide treatment will be used, specify product(s):	
v. Describe any proposed reclamation/mitigation following disturbance:	
c. Will the proposed action use, or create a new demand for water?	
If Yes: i. Total anticipated water usage/demand per day: 3,480 gallons/day	
 i. Total anticipated water usage/demand per day:	✓ Yes □No
If Yes:	<u> </u>
Name of district or service area: Consolidated Water #1	
Does the existing public water supply have capacity to serve the proposal?	✓ Yes ✓ No
• Is the project site in the existing district?	✓ Yes No
Is expansion of the district needed?	∐ Yes No
• Do existing lines serve the project site?	☑ Yes ☐ No
iii. Will line extension within an existing district be necessary to supply the project?	☐Yes ∏ No
If Yes:	
Describe extensions or capacity expansions proposed to serve this project:	
Source(s) of supply for the district:	
<i>iv.</i> Is a new water supply district or service area proposed to be formed to serve the project site?	☐ Yes ✓ No
If, Yes:	
Date application submitted or anticipated:	
Proposed source(s) of supply for new district:	
v. If a public water supply will not be used, describe plans to provide water supply for the project:	
vi. If water supply will be from wells (public or private), what is the maximum pumping capacity:	gallons/minute.
d. Will the proposed action generate liquid wastes?	✓ Yes No
If Yes:	
. Total anticipated liquid waste generation per day: 3,480 gallons/day	
ii. Nature of liquid wastes to be generated (e.g., sanitary wastewater, industrial; if combination, describe all	components and
approximate volumes or proportions of each): Sanitary wastewater	
iii. Will the proposed action use any existing public wastewater treatment facilities?	☐ Yes No
If Yes:	
Name of wastewater treatment plant to be used:	
Name of district:	□sr □sr
Does the existing wastewater treatment plant have capacity to serve the project?	☐ Yes ☐ No
Is the project site in the existing district?	☐ Yes ☐No ☐ Yes ☐No
Is expansion of the district needed?	[] 1 65 [] 140

	 Do existing sewer lines serve the project site? Will a line extension within an existing district be necessary to serve the project? If Yes: Describe extensions or capacity expansions proposed to serve this project: 	☐Yes ☑No ☐Yes ☑No
	Vill a new wastewater (sewage) treatment district be formed to serve the project site? f Yes: Applicant/sponsor for new district:	□Yes ☑ No
1	 Date application submitted or anticipated: What is the receiving water for the wastewater discharge? f public facilities will not be used, describe plans to provide wastewater treatment for the project, including spectreceiving water (name and classification if surface discharge or describe subsurface disposal plans): on-site subsurface septic fields. 	
vi. I	Describe any plans or designs to capture, recycle or reuse liquid waste:	
S	Vill the proposed action disturb more than one acre and create stormwater runoff, either from new point ources (i.e. ditches, pipes, swales, curbs, gutters or other concentrated flows of stormwater) or non-point source (i.e. sheet flow) during construction or post construction?	☑ Yes □ No
<i>i</i> . I	How much impervious surface will the project create in relation to total size of project parcel? +686,063 Square feet or +15.75 acres (impervious surface) +1,533,60(Square feet or +35.21 acres (parcel size)	
ii. I	Describe types of new point sources. New point sources of stormwater runoff include building gutters and driveway curbin	9.
iii.	Where will the stormwater runoff be directed (i.e. on-site stormwater management facility/structures, adjacent p groundwater, on-site surface water or off-site surface waters)? Site runoff will be directed to on-site retention ponds that will control the rate of runoff to pre-developed conditions.	properties,
	If to surface waters, identify receiving water bodies or wetlands:	
iv.]	• Will stormwater runoff flow to adjacent properties? Does the proposed plan minimize impervious surfaces, use pervious materials or collect and re-use stormwater?	Yes No
f. I	Does the proposed action include, or will it use on-site, one or more sources of air emissions, including fuel ombustion, waste incineration, or other processes or operations?	□Yes ☑ No
If Y	'es, identify: Mobile sources during project operations (e.g., heavy equipment, fleet or delivery vehicles)	
ii.	Stationary sources during construction (e.g., power generation, structural heating, batch plant, crushers)	
iii.	Stationary sources during operations (e.g., process emissions, large boilers, electric generation)	
С	Will any air emission sources named in D.2.f (above), require a NY State Air Registration, Air Facility Permit, or Federal Clean Air Act Title IV or Title V Permit?	□Yes☑No
la	s the project site located in an Air quality non-attainment area? (Area routinely or periodically fails to meet	□Yes□No
ii. I	n addition to emissions as calculated in the application, the project will generate: Tons/year (short tons) of Carbon Dioxide (CO ₂)	
	•Tons/year (short tons) of Nitrous Oxide (N2O)	
	 Tons/year (short tons) of Perfluorocarbons (PFCs) Tons/year (short tons) of Sulfur Hexafluoride (SF₆) 	
	 Tons/year (short tons) of Carbon Dioxide equivalent of Hydroflourocarbons (HFCs) Tons/year (short tons) of Hazardous Air Pollutants (HAPs) 	

h. Will the proposed action generate or emit methane (including, but not limited to, sewage treatment plants, landfills, composting facilities)? If Yes: i. Estimate methane generation in tons/year (metric):
ii. Describe any methane capture, control or elimination measures included in project design (e.g., combustion to generate heat or electricity, flaring):
i. Will the proposed action result in the release of air pollutants from open-air operations or processes, such as quarry or landfill operations? If Yes: Describe operations and nature of emissions (e.g., diesel exhaust, rock particulates/dust):
j. Will the proposed action result in a substantial increase in traffic above present levels or generate substantial new demand for transportation facilities or services? If Yes: i. When is the peak traffic expected (Check all that apply): ☐ Morning ☐ Evening ☐ Weekend ☐ Randomly between hours of ☐ to ☐ ii. For commercial activities only, projected number of truck trips/day and type (e.g., semi trailers and dump trucks): ☐ iii.
 iii. Parking spaces: Existing Proposed Net increase/decrease
k. Will the proposed action (for commercial or industrial projects only) generate new or additional demand for energy? If Yes: i. Estimate annual electricity demand during operation of the proposed action: TBD ii. Anticipated sources/suppliers of electricity for the project (e.g., on-site combustion, on-site renewable, via grid/local utility, or other): Grid/local utility
iii. Will the proposed action require a new, or an upgrade, to an existing substation? 1. Hours of operation. Answer all items which apply. i. During Construction: Monday - Friday: 8:00 AM10:00 PM Saturday: 8:00 AM10:00 PM Sunday: 8:00 AM10:00 PM Holidays: 8:00 AM10:00 PM Holidays: As required Holidays: As required

m. Will the proposed action produce noise that will exceed existing ambient noise levels during construction, operation, or both?	✓ Yes ☐ No
If yes:	
i. Provide details including sources, time of day and duration:	
Construction equipment and tools at times permitted by Town Code.	
ii. Will the proposed action remove existing natural barriers that could act as a noise barrier or screen?	∐Yes √ No
Describe:	
	✓ Yes No
n. Will the proposed action have outdoor lighting?	MI 102
If yes:	
i. Describe source(s), location(s), height of fixture(s), direction/aim, and proximity to nearest occupied structures:	
Parking lot and security lighting as permitted by Town Code.	
ii. Will proposed action remove existing natural barriers that could act as a light barrier or screen?	☐ Yes ☑ No
Describe:	
	Dv. Ov.
o. Does the proposed action have the potential to produce odors for more than one hour per day?	☐ Yes Ø No
If Yes, describe possible sources, potential frequency and duration of odor emissions, and proximity to nearest	
occupied structures:	
•	
	-
p. Will the proposed action include any bulk storage of petroleum (combined capacity of over 1,100 gallons)	☐ Yes ☑ No
or chemical products 185 gallons in above ground storage or any amount in underground storage?	
If Yes:	
i. Product(s) to be stored	
iii. Generally, describe the proposed storage facilities:	
m. Generally, describe the proposed storage facilities.	
q. Will the proposed action (commercial, industrial and recreational projects only) use pesticides (i.e., herbicides,	✓ Yes No
insecticides) during construction or operation?	
If Yes:	
i. Describe proposed treatment(s):	
Landscape maintenance and pest control as required.	
" Will de and de and Latendard Doot Managament Procince?	✓ Yes ☐ No
ii. Will the proposed action use Integrated Pest Management Practices?	
r. Will the proposed action (commercial or industrial projects only) involve or require the management or disposal	I CS IIIO
of solid waste (excluding hazardous materials)?	
If Yes:	
i. Describe any solid waste(s) to be generated during construction or operation of the facility:	
Construction: TBD tons per TBD (unit of time)	
• Operation: 20-25 tons per month (unit of time)	
ii. Describe any proposals for on-site minimization, recycling or reuse of materials to avoid disposal as solid waste	:
Construction: Debris recycling will be in accordance with all applicable local requirements.	
Construction, Debtia recycling will be in decordance with all approach result requirements.	
D. P. W. L. Sandana With County and improved	
Operation: Recyling will be in accordance with County requirements.	
iii. Proposed disposal methods/facilities for solid waste generated on-site:	
Construction: Private carter.	
Operation: Private carter.	
Operation (2000)	


s. Does the proposed action include construction or modi	fication of a solid waste mana	gement facility?	☐ Yes 🔽 No
If Yes:			
i. Type of management or handling of waste proposed for the site (e.g., recycling or transfer station, composting, landfill, or			
other disposal activities):			
Afficipated rate of disposal/processing. Tons/month, if transfer or other non-output from the control of the control	combustion/thermal treatment	Of	
Tons/hour, if combustion or thermal	treatment	, 01	
iii. If landfill, anticipated site life:	years		
t. Will the proposed action at the site involve the commen	unial companion tractment at	ross or disposal of horserd	ous Vos (No
t. Will the proposed action at the site involve the commer waste?	rcial generation, treatment, sic	orage, or disposal of nazard	ous respino
If Yes:			
<i>i.</i> Name(s) of all hazardous wastes or constituents to be	generated, handled or manag	ed at facility:	
, , , , , , , , , , , , , , , , , , ,			
ii. Generally describe processes or activities involving h	nazardous wastes or constituer	its:	
iii. Specify amount to be handled or generatedto	ons/month		
iv. Describe any proposals for on-site minimization, rec	veling or reuse of hazardous o	onstituents:	
iv. Describe any proposans for on-site minimization, rec	yeiling of rease of mazardous e		
v. Will any hazardous wastes be disposed at an existing	g offsite hazardous waste facil	ity?	☐Yes☐No
If Yes: provide name and location of facility:			
If No: describe proposed management of any hazardous	t.ahigh will not be cont	to a hazardova viasto facilit	
If No: describe proposed management of any nazardous	wastes which will not be sent	io a nazardous wasie facini	.y .
E. Site and Setting of Proposed Action			
E.1. Land uses on and surrounding the project site			
a. Existing land uses.			
i. Check all uses that occur on, adjoining and near the project site.			
☐ Urban ☐ Industrial ☐ Commercial ☐ Resid	dential (suburban)	(non-farm)	
Forest Agriculture Aquatic Other	r (specity):		
ii. If mix of uses, generally describe:			
b. Land uses and covertypes on the project site.			
Land use or	Current	Acreage After	Change
Covertype	Acreage	Project Completion	(Acres +/-)
Roads, buildings, and other paved or impervious	0.04	15.75	+15.71
surfaces	05.00	4.50	24.40
• Forested	25.96	1.50	-24.46
Meadows, grasslands or brushlands (non- agricultural, including abandoned agricultural)	7.93	7.95	+0.02
Agricultural		_	<u>g</u>
(includes active orchards, field, greenhouse etc.)	0	0	0
Surface water features		4.50	.4.50
(lakes, ponds, streams, rivers, etc.)	0	1.50	+1.50
Wetlands (freshwater or tidal)	1.28	1.28	0
Non-vegetated (bare rock, earth or fill)	0	0	0
• Other	0	7.23	+7.23
Describe: Landscaping	J	1.20	

d. Are there any facilities serving children, the elderly, people with disabilities (e.g., schools, hospitals, licensed day care centers, or group homes) within 1500 feet of the project site? If Yes, i. Identify Facilities: e. Does the project site contain an existing dam? If Yes: i. Dimensions of the dam and impoundment: • Dam height: • Dam length: • Dam length: • Dam length: • Dam length: • Surface area: • Volume impounded: gallons OR aere-feet ii. Dam's existing hazard classification: iii. Provide date and summarize results of last inspection: If Yes: i. Has the project site ever been used as a municipal, commercial or industrial solid waste management facility, or does the project site adjoin property which is now, or was at one time, used as a solid waste management facility? If Yes: i. Has the facility been formally closed? • If yes, cite sources/documentation: iii. Describe the location of the project site relative to the boundaries of the solid waste management facility: iii. Describe any development constraints due to the prior solid waste activities: g. Have hazardous wastes been generated, treated and/or disposed of at the site, or does the project site adjoin property which is now or was at one time used to commercially treat, store and/or dispose of hazardous waste? If Yes: i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred: h. Potential contamination history. Has there been a reported spill at the proposed project site, or have any remedial actions been conducted at or adjacent to the proposed site? If Yes: i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred: Yes No remedial actions been conducted at or adjacent to the proposed site? Yes No waste	c. Is the project site presently used by members of the community for public recreation? i. If Yes: explain:	☐ Yes ✓ No
e. Does the project site contain an existing dam? If Yes: i. Dimensions of the dam and impoundment: • Dam height: • Dam length: • Surface area: • Volume impounded: iii. Provide date and summarize results of last inspection: f. Has the project site ever been used as a municipal, commercial or industrial solid waste management facility, or does the project site adjoin property which is now, or was at one time, used as a solid waste management facility? If Yes: i. Has the facility been formally closed? • If yes, cite sources/documentation: iii. Describe the location of the project site relative to the boundaries of the solid waste management facility: iii. Describe any development constraints due to the prior solid waste activities: g. Have hazardous wastes been generated, treated and/or disposed of at the site, or does the project site adjoin property which is now or was at one time used to commercially treat, store and/or dispose of hazardous waste? If Yes: i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred: h. Potential contamination history. Has there been a reported spill at the proposed project site, or have any remedial actions been conducted at or adjacent to the proposed site? If Yes: i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred: h. Potential contamination history. Has there been a reported spill at the proposed project site, or have any remedial actions been conducted at or adjacent to the proposed site? If Yes: i. Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site memediation database? Check all that apply: Yes = Spills Incidents database Provide DEC ID number(s): No the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database? Yes = Does No the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database? Yes = Does No the pr	d. Are there any facilities serving children, the elderly, people with disabilities (e.g., schools, hospitals, licensed day care centers, or group homes) within 1500 feet of the project site? If Yes,	☐ Yes ☑ No
If Yes: i. Dimensions of the dam and impoundment: • Dam height: • Dam length: • Surface area: • Volume impounded: ii. Dam's existing hazard classification: iiii. Provide date and summarize results of last inspection: Interpretation Provide Provide Provide		
Dam length: Surface area: Volume impounded: gallons OR acre-feet ii. Dam's existing hazard classification: iii. Provide date and summarize results of last inspection: File	If Yes: i. Dimensions of the dam and impoundment:	Yes No
iii. Provide date and summarize results of last inspection: G. Has the project site ever been used as a municipal, commercial or industrial solid waste management facility, or does the project site adjoin property which is now, or was at one time, used as a solid waste management facility? If Yes: I Has the facility been formally closed?	 Dam length: Surface area: Volume impounded: gallons OR acre-feet 	
or does the project site adjoin property which is now, or was at one time, used as a solid waste management facility? If Yes: i. Has the facility been formally closed? • If yes, cite sources/documentation: ii. Describe the location of the project site relative to the boundaries of the solid waste management facility: iii. Describe any development constraints due to the prior solid waste activities: g. Have hazardous wastes been generated, treated and/or disposed of at the site, or does the project site adjoin property which is now or was at one time used to commercially treat, store and/or dispose of hazardous waste? If Yes: i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred: If Yes: i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred: If Yes: i. Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site Yes No Remediation database? Check all that apply: Yes - Spills Incidents database Provide DEC ID number(s): Yes - Environmental Site Remediation database Provide DEC ID number(s): Neither database Provide DEC ID number(s): Neither database Provide DEC ID number(s): Neither database Provide DEC ID number(s): Provide DEC ID numb		
i. Has the facility been formally closed? • If yes, cite sources/documentation: ii. Describe the location of the project site relative to the boundaries of the solid waste management facility: iii. Describe any development constraints due to the prior solid waste activities: g. Have hazardous wastes been generated, treated and/or disposed of at the site, or does the project site adjoin property which is now or was at one time used to commercially treat, store and/or dispose of hazardous waste? If Yes: i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred: h. Potential contamination history. Has there been a reported spill at the proposed project site, or have any remedial actions been conducted at or adjacent to the proposed site? If Yes: i. Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site	or does the project site adjoin property which is now, or was at one time, used as a solid waste management facil	☐ Yes No lity?
iii. Describe any development constraints due to the prior solid waste activities: g. Have hazardous wastes been generated, treated and/or disposed of at the site, or does the project site adjoin property which is now or was at one time used to commercially treat, store and/or dispose of hazardous waste? If Yes: i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred: h. Potential contamination history. Has there been a reported spill at the proposed project site, or have any remedial actions been conducted at or adjacent to the proposed site? If Yes: i. Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site	i. Has the facility been formally closed?	☐Yes☐ No
g. Have hazardous wastes been generated, treated and/or disposed of at the site, or does the project site adjoin property which is now or was at one time used to commercially treat, store and/or dispose of hazardous waste? If Yes: i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred: h. Potential contamination history. Has there been a reported spill at the proposed project site, or have any remedial actions been conducted at or adjacent to the proposed site? If Yes: i. Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site Remediation database? Check all that apply: Yes — Spills Incidents database Provide DEC ID number(s): Neither database ii. If site has been subject of RCRA corrective activities, describe control measures: iii. Is the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database? Yes No Yes No	ii. Describe the location of the project site relative to the boundaries of the solid waste management facility:	
property which is now or was at one time used to commercially treat, store and/or dispose of hazardous waste? If Yes: i. Describe waste(s) handled and waste management activities, including approximate time when activities occurred: h. Potential contamination history. Has there been a reported spill at the proposed project site, or have any remedial actions been conducted at or adjacent to the proposed site? If Yes: i. Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site Remediation database? Check all that apply: Yes – Spills Incidents database Provide DEC ID number(s): Neither database ii. If site has been subject of RCRA corrective activities, describe control measures: iii. Is the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database? Yes No Yes No Yes No Yes No Yes No Yes No Yes DEC ID number(s):	iii. Describe any development constraints due to the prior solid waste activities:	
remedial actions been conducted at or adjacent to the proposed site? If Yes: i. Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site Remediation database? Check all that apply: Yes – Spills Incidents database Provide DEC ID number(s): Yes – Environmental Site Remediation database Neither database ii. If site has been subject of RCRA corrective activities, describe control measures: iii. Is the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database? If yes, provide DEC ID number(s):	property which is now or was at one time used to commercially treat, store and/or dispose of hazardous waste? If Yes:	
remedial actions been conducted at or adjacent to the proposed site? If Yes: i. Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site Remediation database? Check all that apply: Yes – Spills Incidents database Provide DEC ID number(s): Yes – Environmental Site Remediation database Neither database ii. If site has been subject of RCRA corrective activities, describe control measures: iii. Is the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database? If yes No No If yes, provide DEC ID number(s):		
i. Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site Remediation database? Check all that apply: Yes − Spills Incidents database Provide DEC ID number(s): Neither database ii. If site has been subject of RCRA corrective activities, describe control measures: iii. Is the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database? If yes No No Yes No Yes No Yes No	remedial actions been conducted at or adjacent to the proposed site?	Yes No
☐ Yes - Environmental Site Remediation database Provide DEC ID number(s): ☐ Neither database ii. If site has been subject of RCRA corrective activities, describe control measures: iii. Is the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database? ☐ Yes ☑ No If yes, provide DEC ID number(s): ☐ Yes ☑ No	 i. Is any portion of the site listed on the NYSDEC Spills Incidents database or Environmental Site Remediation database? Check all that apply: 	_
iii. Is the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database? ☐ Yes ✓ No If yes, provide DEC ID number(s):	Yes – Environmental Site Remediation database Provide DEC ID number(s):	
If yes, provide DEC ID number(s):	ii. If site has been subject of RCRA corrective activities, describe control measures:	
iv. If yes to (i), (ii) or (iii) above, describe current status of site(s):	iii. Is the project within 2000 feet of any site in the NYSDEC Environmental Site Remediation database? If yes, provide DEC ID number(s):	☐Yes ☑ No

ν. Is the project site subject to an institutional contr	ol limiting property uses?	☐ Yes ✓ No
If yes, DEC site ID number: Describe the type of institutional control (e)	e.g., deed restriction or easement):	
Describe any use limitations:		
 Describe any engineering controls: 		
Will the project affect the institutional or e		☐ Yes ☐ No
Explain:		
E.2. Natural Resources On or Near Project Site		
a. What is the average depth to bedrock on the proje	ct site? <u>1.2-2.5</u> feet	
b. Are there bedrock outcroppings on the project site	· · · · · · · · · · · · · · · · · · ·	☐ Yes / No
If Yes, what proportion of the site is comprised of be	edrock outcroppings?%	
c. Predominant soil type(s) present on project site:	MdB Mardin gravelly silt loam 35 %	
31 ()1	ANC/AND Arnot-Lordstown complex 40 %	
	SXC Swartswood and Mardin soils 15 %	
d. What is the average depth to the water table on th	e project site? Average: 1.5-6.5+ feet	
e. Drainage status of project site soils: Well Drain		
✓ Moderately ✓ Poorly Dra	y Well Drained: 40 % of site sined 5 % of site	
f. Approximate proportion of proposed action site w		
1. Approximate proportion of proposed action site w	10-15%: 14.18 % of site	
	✓ 10-15%: 18.77 % of site ✓ 15% or greater: 18.77 % of site	
g. Are there any unique geologic features on the pro If Yes, describe:		∐Yes ∏ No
-		
h. Surface water features.		
	ands or other waterbodies (including streams, rivers,	✓ Yes No
ii. Do any wetlands or other waterbodies adjoin the		☑ Yes □ No
If Yes to either <i>i</i> or <i>ii</i> , continue. If No, skip to E.2.i. <i>iii</i> . Are any of the wetlands or waterbodies within o		✓ Yes□No
state or local agency?	r adjoining the project site regulated by any rederal,	Y res_no
iv, For each identified regulated wetland and water	pody on the project site, provide the following information: Classification C	
Lakes or Ponds: Name	Classification Approximate Size	
Wetlands: Name Federal Waters	Approximate Size	
• Wetland No. (if regulated by DEC)	ost recent compilation of NYS water quality-impaired	☐Yes ☑ No
waterbodies?	ost recent compliation of 1413 water quanty-impaned	1 CS140
If yes, name of impaired water body/bodies and basi	s for listing as impaired:	
,		
i. Is the project site in a designated Floodway?		☐Yes ☑No
j. Is the project site in the 100-year Floodplain?		☐Yes No
k. Is the project site in the 500-year Floodplain?		☐Yes No
l. Is the project site located over, or immediately adj If Yes:	oining, a primary, principal or sole source aquifer?	☐Yes Ø No
i. Name of aquifer:		

m. Identify the predominant wildlife species that occupy or use the project site: Typical suburban species	
n. Does the project site contain a designated significant natural community? If Yes: i. Describe the habitat/community (composition, function, and basis for designation):	∏Yes √ No
ii. Source(s) of description or evaluation: iii. Extent of community/habitat: Currently: Following completion of project as proposed: Gain or loss (indicate + or -): acres acres	
 o. Does project site contain any species of plant or animal that is listed by the federal government or NYS as endangered or threatened, or does it contain any areas identified as habitat for an endangered or threatened spec If Yes: Species and listing (endangered or threatened): 	
p. Does the project site contain any species of plant or animal that is listed by NYS as rare, or as a species of special concern? If Yes:	Yes √ No
i. Species and listing:	
q. Is the project site or adjoining area currently used for hunting, trapping, fishing or shell fishing? If yes, give a brief description of how the proposed action may affect that use:	∐Yes √ No
E.3. Designated Public Resources On or Near Project Site	
a. Is the project site, or any portion of it, located in a designated agricultural district certified pursuant to Agriculture and Markets Law, Article 25-AA, Section 303 and 304? If Yes, provide county plus district name/number:	∐Yes √ No
b. Are agricultural lands consisting of highly productive soils present? i. If Yes: acreage(s) on project site? ii. Source(s) of soil rating(s):	∐Yes √ No
c. Does the project site contain all or part of, or is it substantially contiguous to, a registered National Natural Landmark? If Yes: i. Nature of the natural landmark: ii. Provide brief description of landmark, including values behind designation and approximate size/extent:	_Yes √ No
d. Is the project site located in or does it adjoin a state listed Critical Environmental Area? If Yes: i. CEA name: ii. Basis for designation: iii. Designating agency and date:	

e. Does the project site contain, or is it substantially contiguous to, a building, archaeological site, or district which is listed on the National or State Register of Historic Places, or that has been determined by the Con Office of Parks, Recreation and Historic Preservation to be eligible for listing on the State Register of Historic If Yes:	
 i. Nature of historic/archaeological resource: Archaeological Site Historic Building or District ii. Name: Historic Building or District iii. Brief description of attributes on which listing is based; 	
f. Is the project site, or any portion of it, located in or adjacent to an area designated as sensitive for archaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory?	✓ Yes No
 g. Have additional archaeological or historic site(s) or resources been identified on the project site? If Yes: i. Describe possible resource(s): 	∐Yes √ No
ii. Basis for identification:	
h. Is the project site within fives miles of any officially designated and publicly accessible federal, state, or lo scenic or aesthetic resource? If Yes:	
i. Identify resource:ii. Nature of, or basis for, designation (e.g., established highway overlook, state or local park, state historic t etc.):	trail or scenic byway,
etc.): miles.	
 i. Is the project site located within a designated river corridor under the Wild, Scenic and Recreational River Program 6 NYCRR 666? If Yes: i. Identify the name of the river and its designation: 	rs ∏Yes √ No
i. Identify the name of the river and its designation:ii. Is the activity consistent with development restrictions contained in 6NYCRR Part 666?	∐Yes ☐No
F. Additional Information Attach any additional information which may be needed to clarify your project.	
If you have identified any adverse impacts which could be associated with your proposal, please describe the measures which you propose to avoid or minimize them.	nose impacts plus any
G. Verification I certify that the information provided is true to the best of my knowledge. JMC Planning Engineering Landscape Applicant/Sponsor Name Architecture & Land Surveying, PLLC Date 1/22/2021	
Signature	



B.i.i [Coastal or Waterfront Area]	No
B.i.ii [Local Waterfront Revitalization Area]	No
C.2.b. [Special Planning District]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.1.h [DEC Spills or Remediation Site - Potential Contamination History]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.1.h.i [DEC Spills or Remediation Site - Listed]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.1.h.i [DEC Spills or Remediation Site - Environmental Site Remediation Database]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.1.h.iii [Within 2,000' of DEC Remediation Site]	No
E.2.g [Unique Geologic Features]	No
E.2.h.i [Surface Water Features]	Yes
E.2.h.ii [Surface Water Features]	Yes
E.2.h.iii [Surface Water Features]	Yes - Digital mapping information on local and federal wetlands and waterbodies is known to be incomplete. Refer to EAF Workbook.
E.2.h.iv [Surface Water Features - Stream Name]	862-231
E.2.h.iv [Surface Water Features - Stream Classification]	С
E.2.h.iv [Surface Water Features - Wetlands Name]	Federal Waters
E.2.h.v [Impaired Water Bodies]	No
E.2.i. [Floodway]	No
E.2.j. [100 Year Floodplain]	No
E.2.k. [500 Year Floodplain]	No

E.2.I. [Aquifers]	No
E.2.n. [Natural Communities]	No
E.2.o. [Endangered or Threatened Species]	No
E.2.p. [Rare Plants or Animals]	No
E.3.a. [Agricultural District]	No
E.3.c. [National Natural Landmark]	No
E.3.d [Critical Environmental Area]	No
E.3.e. [National or State Register of Historic Places or State Eligible Sites]	Digital mapping data are not available or are incomplete. Refer to EAF Workbook.
E.3.f. [Archeological Sites]	Yes
E.3.i. [Designated River Corridor]	No

FARRELL INDUSTRIAL PARK

TAX MAP SECTION 34 | BLOCK 2 | LOT 45 ROUTE 300 TOWN OF NEWBURGH, NY TOWN OF NEWBURGH PROJECT NO. 2020-16

FARRELL BUILDING COMPANY 2317 MONTAUK HIGHWAY BRIDGEHAMPTON, NY 11932 631-766-0023

CHUN S. MCGLASSON 16 ANNA COURT

CARMEL, NY 10512

STANELY A. SCHUTZMAN, P.C. **ROCKLAND COUNTY OFFICE:** DUTCHESS COUNTY OFFICE: 61 S. MAIN STREET P.O. BOX 969 NEW CITY, N.Y. 10956 POUGHKEEPSIE, N.Y. 12602

PHONE: (845) 600-8LAW (8529)

Site Planner, Civil & Traffic Engineer, Surveyor and Landscape Architect:

JMC PLANNING ENGINEERING LANDSCAPE ARCHITECTURE & LAND SURVEYING PLLC: 120 BEDFORD ROAD ARMONK, NY 10504 914-273-5225




NEWTOWN, CT 06470 203-364-9460





Geotechnical Engineer: CARLIN-SIMPSON & ASSOCIATES 1 MAIN STREET SAYREVILLE, NJ 08872 732-432-5757

Natural Resources Consultant: ECOLOGICAL SOLUTIONS, LLC 1248 SOUTHFORD ROAD SOUTHBURY, CT 06488 203-910-4716














LEGEND











JMC Drawing List

C-000 COVER SHEET

C-010 EXISTING CONDITIONS MAP AND SITE REMOVALS PLAN

C-100 LAYOUT PLAN C-110 PRELIMINARY LOT CONSOLIDATION & SUBDIVISION PLAN

C-200 GRADING PLAN C-210 DRIVEWAY PROFILE

C-300 UTILITIES PLAN

C-310 ON SITE WASTEWATER TREATMENT SYSTEM PLAN

C-400 EROSION AND SEDIMENT CONTROL PLAN

C-600 LIGHTING PLAN C-700 TRUCK TURNING PLAN

C-900 CONSTRUCTION DETAILS C-901 CONSTRUCTION DETAILS

C-902 CONSTRUCTION DETAILS

C-903 CONSTRUCTION DETAILS

C-904 CONSTRUCTION DETAILS

C-905 CONSTRUCTION DETAILS (OWTS) C-906 CONSTRUCTION DETAILS (SITE ENTRANCE)

C-907 CONSTRUCTION DETAILS (SITE ENTRANCE) L-100 LANDSCAPE PLAN

L-900 LANDSCAPE DETAILS

Claris Design Build Drawing List:

A101 FLOOR PLANS BUILDINGS A & B

A102 SIGN DETAILS A201 BUILDING A ELEVATIONS

A202 BUILDING B ELEVATIONS

A203 RENDERINGS

TABLE OF LAND USE SECTION 34, BLOCK 2, LOT 45(1) ZONE "IB" - "INTERCHANGE BUSINESS"

PROPOSED USE: WAREHOUSE (D9)
PROPOSED ACCESSORY USES: OFF STREET PARKING (A4), TRUCK LOADING FACILITIES (A5) FIRE DISTRICT: CRONOMER VALLEY WATER DISTRICT: NEWBURGH

SCHOOL DISTRICT: NEWBURGH								
DESCRIPTION		R	EQUIRE	D	EXISTING	Pf	ROPOSE	ED
LOT AREA	(SQUARE FEET)		44,000		±1,545,969 ⁽¹⁾	N	O CHANG	E ⁽¹⁾
LOT WIDTH	(FEET)		150		±965		O CHANG	
LOT DEPTH	(FEET)		150		±1,311	N	NO CHANGE	
LOT BUILDING COVERAGE	(PERCENT)	40 N/A ⁽²⁾ 18.76 ⁽³⁾						
BUILDING HEIGHT	(FEET)		40		N/A ⁽²⁾		49 ⁽⁴⁾	
LOT SURFACE COVERAGE	(PERCENT)		80		N/A ⁽²⁾	45.48 ⁽⁵⁾)
YARDS								
FRONT BUILDING SETBACK	(FEET)		60 ⁽⁶⁾		N/A ⁽²⁾		±329	
REAR BUILDING SETBACK	(FEET)		60		N/A ⁽²⁾		±454	
SIDE BUILDING SETBACK	(FEET)	3	50/80/22	8 ⁽⁷⁾	N/A ⁽²⁾	±1	05/346/2	241 ⁽⁷⁾
SIDE YARD BUFFER (8)	(FEET)		100		N/A ⁽²⁾		±100	
PARKING SUMMARY		BLDG A	BLDG B	TOTAL		BLDG A	BLDG B	TOTAL
TOTAL SPACES	(SPACES)	124 ₍₁₀₎	70 (9)	194 ₍₁₀₎	N/A ⁽²⁾	129	122	251
STANDARD SPACES	(SPACES)	119	67	186	N/A ⁽²⁾	124	117	241
HANDICAP SPACES	(SPACES)	5 ⁽¹¹⁾	3 ⁽¹¹⁾	8 ⁽¹¹⁾	N/A ⁽²⁾	5	5	10
LOADING SPACES	(SPACES)	6 ⁽¹²⁾	4 ⁽¹²⁾	10 ⁽¹²⁾	N/A ⁽²⁾	44	28	72
TRUCK/TRAILER SPACE	(SPACES)	N/A ⁽²⁾	N/A ⁽²⁾	N/A ⁽²⁾	N/A ⁽²⁾	22	18	40

(1) THE SITE IS ONE TAX LOT THAT INCLUDES TWO PARCELS. THE TWO EXISTING PARCELS WILL BE MERGED THROUGH THE OFFICE OF THE TAX ASSESSOR AT THE APPROPRIATE TIME.

(2) NOT APPLICABLE

TOTAL BUILDING AREA - 185,000 S.F. (BUILDING A) + 105,000 S.F. (BUILDING B) = 290,000 S.F. BUILDING COVERAGE - TOTAL BUILDING AREA/LOT AREA = 290,000 S.F./1,545,969 S.F. = 18.76%

(4) THE BUILDING HEIGHT SHOWN ACCOUNTS FOR THE GRADING REQUIRED TO ACCOMMODATE LOADING AREAS FOR THE WAREHOUSES. THE ACTUAL HEIGHT OF THE BUILDING, WITHOUT CONSIDERATION OF THE AVERAGE GRADE IS 45 FEET (A 42 FT HIGH FLAT ROOF AND A 3 FT PARAPET — SEE ARCHITECTURAL DRAWINGS.) THE AVERAGE GRADE AT EACH BUILDING HAS BEEN CALCULATED BY MEASURING THE FINISHED GRADE ALONG THE FACADE FACING THE STREET AT 50 FOOT INCREMENTS AND FINDING THE AVERAGE ELEVATION AS FOLLOWS: BUILDING A = (452 + 452 + 456 + 456 + 456 + 456 + 456 + 456 + 456 + 456 + 456 + 456 + 456 + 456 + 456 + 451) / 16 = 455.2BUILDING B = (456 + 452 + 452 + 452 + 452 + 452 + 452 + 452 + 452 + 452 + 450) / 11 = 452.2THE BUILDING HEIGHT FOR EACH BUILDING WAS THEN CALCULATED BY DETERMINING THE DIFFERENCE BETWEEN THE AVERAGE GRADE AND THE FINISHED FLOOR ELEVATION, THEN ADDING THE DIFFERENCE TO THE ACTUAL BUILDING HEIGHT AS FOLLOWS:

ACCORDINGLY, FOR THE PURPOSE OF THIS APPLICATION THE BUILDING HEIGHTS FOR BUILDINGS A AND B ARE 46 AND 49 RESPECTIVELY. A VARIANCE IS REQUIRED AND WILL BE

(5) THE LOT SURFACE COVERAGE WAS CALCULATED AS FOLLOWS: TOTAL COVERAGE AREA - 185,000 S.F. (BUILDING A) + 105,000 S.F. (BUILDING B) + 413,062 (PAVEMENT & SIDEWALKS) = 703,062 S.F. SURFACE COVERAGE - TOTAL COVERAGE AREA/LOT AREA = 703,062 S.F./1,545,969 S.F. = 45.48%

(6) PURSUANT TO SECTION 185-18.C.4.(b). OF THE TOWN CODE, FRONT YARDS ABUTTING A STATE HIGHWAY SHALL BE AT LEAST 60 FEET.


(7) PURSUANT TO THE TABLE OF USE AND BULK REQUIREMENTS FOR THE IB DISTRICT, THE MINIMUM SIDE YARD DIMENSION SHALL BE 30 FEET AND THE MINIMUM DIMENSION FOR BOTH SIDE YARDS SHALL BE 80 FEET. PURSUANT TO SECTION 185-18.C.5. OF THE TOWN CODE, SIDE YARDS OF A LOT IN THE IB DISTRICT ABUTTING A RESIDENTIAL DISTRICT WITH A TOTAL BUILDING FLOOR AREA BETWEEN 250,000 S.F. AND 500,000 S.F. SHALL HAVE A SETBACK OF 200 FEET, PLUS AN ADDITIONAL 2 FEET FOR EACH FOOT OF BUILDING HEIGHT OVER 35 FEET. THE NUMBERS PROVIDED ARE "ONE SIDE YARD/BOTH SIDE YARDS/SIDE YARD ADJACENT TO A RESIDENTIAL DISTRICT."


(8) PURSUANT TO SECTION 185-21.D.2. OF THE TOWN CODE, SITES IN THE IB ZONE THAT ARE ADJACENT TO A RESIDENTIAL ZONE SHALL HAVE A BUFFER STRIP OF 75 FEET. PURSUANT TO SECTION 185-21.D.3., THE BUFFER SHALL BE INCREASED TO 100 FEET. PURSUANT TO SECTION 185-21.E.6., THE 40 FEET CLOSEST TO THE PROPERTY LINE SHALL REMAIN UNDISTURBED IN ITS EXISTING VEGETATIVE STATE AND THE REMAINING 60 FEET SHALL BE ENHANCED.

(9) SINCE THE ENDUSER OF THE PROPOSED WAREHOUSE IS UNKNOWN AT THIS TIME, THE ANTICIPATED NUMBER OF EMPLOYEES HAS BEEN CALCULATED BASED UPON THE ENERGYSTAR.GOV "WAREHOUSE SPACE USE INFORMATION" AND "WAREHOUSE DATA TRENDS", WHICH INDICATES AN AVERAGE OCCUPANT DENSITY FOR THE TOTAL NUMBER OF EMPLOYEES OF 0.5 OCCUPANTS PER 1,000 S.F. AND A 95TH PERCENTILE OF 1.5 EMPLOYEES PER 1,000 S.F. FOR THE PURPOSE OF THIS APPROVAL, IT HAS BEEN CONSERVATIVELY ASSUMED THAT THIS FACILITY WILL OPERATE WITH 1 EMPLOYEE PER 1,000 S.F. BASED UPON THIS, BUILDING A WILL HAVE 185 EMPLOYEES AND BUILDING B WILL HAVE 105

EMPLOYEES, FOR A TOTAL OF 290 EMPLOYEES. (10) THE TOWN PARKING REQUIREMENT IS 2 SPACES PER 3 EMPLOYEES. THEREFORE, BUILDING A REQUIRES 124 PARKING SPACES (185/3 = 61.66) (61.66 X 2 = 123.32). BUILDING B REQUIRES 70 PARKING SPACES (105/3 = 35 (35 X 2 = 70). FOR A TOTAL REQUIRED PARKING SPACES OF 194.

(11) IN ACCORDANCE WITH ADA REQUIREMENTS, BUILDING A, WHICH REQUIRES 123.32 PARKING SPACES NEEDS 5 HANDICAP PARKING SPACES. BUILDING B, WHICH REQUIRES 70 PARKING SPACES NEEDS 3 HANDICAP PARKING SPACES, RESULTING IN A TOTAL REQUIRED HANDICAP PARKING SPACES OF 8. (12) THE TOWN LOADING REQUIREMENT IS 2 SPACES FOR THE FIRST 40,000 S.F. AND ONE ADDITIONAL FOR EACH ADDITIONAL 40,000 S.F. THEREFORE, BUILDING A (185,000 S.F.) REQUIRES 6 LOADING SPACES (185,000 - 40,000 = 145,000) (145,000/40,000 = 3.62) (2 + 3.62 = 5.62). BUILDING B (105,000 S.F.) REQUIRES 4 LOADING SPACES (105,000 -40,000 = 65,000) (65,000/40,000 = 1.625) (2 + 1.625 = 3.625) FOR A TOTAL REQUIRED LOADING SPACES OF 10.





Previous Editions Obsolete



EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2. NOT TO SCALE ^{roject No:} 18156 18156-COVER COVER COVER.scr

ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND

REPORTS BEARING THE SEAL

OF A LICENSED PROFESSIONAL

ENGINEER OR LICENSED LAND

SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW

YORK STATE EDUCATION LAW,

REPRESENTATIVE, JMC, PLLC AND THE APPLICABLE MUNICIPALITY OR AGENCY SHALL BE NOTIFIED IN WRITING. THE EXISTING/PROPOSED UTILITIES RELOCATION SHALL BE DESIGNED BY JMC, PLLC. 4. ALL WORK SHALL BE DONE IN STRICT COMPLIANCE WITH ALL APPLICABLE NATIONAL, STATE, AND LOCAL CODES, STANDARDS, ORDINANCES, RULES, AND REGULATIONS. ALL CONSTRUCTION WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL SAFETY CODES. APPLICABLE SAFETY CODES MEAN THE LATEST EDITION INCLUDING ANY AND ALL AMENDMENTS, REVISIONS, AND ADDITIONS THERETO, TO THE FEDERAL DEPARTMENT OF LABOR, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION'S OCCUPATIONAL SAFETY AND HEALTH STANDARDS (OSHA); AND APPLICABLE SAFETY, HEALTH REGULATIONS AND BUILDING CODES FOR

CONSTRUCTION IN THE STATE OF NEW YORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR GUARDING AND PROTECTING ALL OPEN EXCAVATIONS IN ACCORDANCE WITH THE PROVISION OF SECTION 107-05 (SAFETY AND HEALTH REQUIREMENTS) OF THE NYSDOT STANDARD SPECIFICATIONS. IF THE CONTRACTOR PERFORMS ANY HAZARDOUS CONSTRUCTION PRACTICES, ALL OPERATIONS IN THE AFFECTED ARÉA SHALL BE DISCONTINUED AND IMMEDIATE ACTION SHALL BE TAKEN TO CORRECT THE SITUATION TO THE SATISFACTION OF THE APPROVAL AUTHORITY HAVING JURISDICTION. 5. CONTRACTOR SHALL MAINTAIN ACCESS TO ALL PROPERTIES AFFECTED BY THE SCOPE OF WORK SHOWN HEREON AT ALL TIMES TO THE SATISFACTION OF THE OWNERS REPRESENTATIVE. RAMPING CONSTRUCTION TO PROVIDE ACCESS MAY BE CONSTRUCTED WITH SUBBASE MATERIAL EXCEPT THAT TEMPORARY ASPHALT

CONCRETE SHALL BE PLACED AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SAFE PEDESTRIAN ACCESS AT ALL TIMES. 6. CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF EXISTING PAVEMENT TO REMAIN.

1. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL CALL 811 "DIG SAFELY" (1-800-962-7962) TO HAVE UNDERGROUND UTILITIES LOCATED, EXPLORATORY EXCAVATIONS SHALL COMPLY WITH CODE 753 REQUIREMENTS. NO WORK SHALL COMMENCE UNTIL ALL THE OPERATORS HAVE NOTIFIED THE CONTRACTOR THAT THEIR UTILITIES HAVE BEEN LOCATED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PRESERVATION OF ALL PUBLIC AND PRIVATE UNDERGROUND AND SURFACE UTILITIES AND STRUCTURES AT OR ADJACENT TO THE SITE OF CONSTRUCTION, INSOFAR AS THEY MAY BE ENDANGERED BY THE CONTRACTOR'S OPERATIONS. THIS SHALL HOLD TRUE WHETHER OR NOT THEY ARE SHOWN ON THE CONTRACT DRAWINGS. IF THEY ARE SHOWN ON THE DRAWINGS, THEIR LOCATIONS ARE NOT GUARANTEED EVEN THOUGH THE INFORMATION WAS OBTAINED FROM THE BEST AVAILABLE SOURCES, AND IN ANY EVENT, OTHER UTILITIES ON THESE PLANS MAY BE ENCOUNTERED IN THE FIELD. THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, IMMEDIATELY REPAIR OR REPLACE ANY STRUCTURES OR UTILITIES THAT HE DAMAGES,

2. CONTRACTOR SHALL HAND DIG TEST PITS TO VERIFY THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES PRIOR TO THE START OF CONSTRUCTION.

CONTRACTOR SHALL VERIFY EXISTING UTILITIES DEPTHS AND ADVISE OF ANY CONFLICTS WITH PROPOSED UTILITIES. IF CONFLICTS ARE PRESENT. THE OWNER'S FIELD

GENERAL CONSTRUCTION NOTES APPLY TO ALL WORK HEREIN:

3. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ANY AND ALL LOCAL PERMITS REQUIRED.

AND SHALL CONSTANTLY PROCEED WITH CAUTION TO PREVENT UNDUE INTERRUPTION OF UTILITY SERVICE.



ENGINEERING, LANDSCAPE ARCHITECTURE & LAND SURVEYING, PLLC., LAST REVISED 10/29/2020. CONTRACTOR SHALL SATISFY HIM/HERSELF AS TO THE ACCURACY OF THE EXISTING INFORMATION SHOWN HEREON AND IDENTIFY ANY

ACCORDANCE WITH THE ARMY CORPS OF ENGINEERS (USACE) WETLANDS DELINEATION MANUAL (JANUARY 1987), ROUTINE DETERMINATION METHOD AND NORTHCENTRAL/NORTHEAST SUPPLEMENT. THE WETLANDS WERE DELINEATED ON

SOIL AND FOUNDATION INVESTIGATION", DATED 10/14/2020, PREPARED BY CARLIN-SIMPSON AND ASSOCIATES, SUPPLEMENTED BY LOCATIONS OBSERVED 4. CONTRACTOR SHALL REFER TO GENERAL CONSTRUCTION NOTES ON DRAWING

DEMOLISHED AND EXISTING UTILITIES TO BE PROTECTED. IF ANY DISCREPANCIES ARE FOUND, THE CONTRACTOR SHALL NOTIFY THE GENERAL CONTRACTOR AND

ALL OTHER AUTHORITIES HAVING JURISDICTION. CONTRACTOR SHALL PAY ALL OUTSTANDING FEES, CHARGES, AND DEPOSITS TO ACQUIRE SAID PERMITS. NO DEMOLITION SHALL COMMENCE UNTIL A PERMIT HAS BEEN OBTAINED FROM THE

11. PRIOR TO THE START OF SITE DEMOLITION, EROSION AND SEDIMENT CONTROL


DEVICES SHALL BE INSTALLED IN ACCORDANCE WITH THE NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL, AS 12. EXISTING DRAINAGE PATTERNS ON SITE SHALL BE MAINTAINED TO THE MAXIMUM


DISTURBED OR DAMAGED DUE TO THE NEW CONSTRUCTION, ARE TO BE REPLACED WITH MATERIALS CONSISTENT WITH EXISTING CONDITIONS. 15. THESE PLANS ARE TO BE PROVIDED TO BOTH THE DEMOLITION CONTRACTOR AND THE SITE CONTRACTOR FOR THEIR USE, INFORMATION AND COORDINATION.

ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY

SECTION 7209, SUBSECTION 2.

Drawn: DK Approved: DL/ Scale: 1" = 50' Project No: 18156 18156-BASE EXIST EXIST.scr







 Drawn:
 TC
 Approved:
 DL/JS


 Scale:
 H:1" = 50'/V:1" = 10'

 Date:
 12/03/2020


 Project No:
 18156

 18156-GRAD
 PROFILE
 GRAD.scr

 Drawing No:
 Drawing No:








ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND

REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.

Scale: 1" = 50' Date: 12/03/2020 , 18156-UTIL UTIL UTIL.scr



INV. 414.49 (15") INV. 414.00 (24") INV. 438.95 (\$5") SMH-½ TOP 451.00 INV. 442.75 (6") NV. 445.25 (15") 104 L.F. 15" HDPE 9 4.16% ALTERNATING CUE BOX TOP 442.00 INV 440.00 (IN) INV 438.00 (OÚT) INV. 449.60 (15") ─19 L.F. 15" HDPE @ 2.12% TORMWATER DISCHARGE — SETBACK 446

PERCOLATION TESTING DATA TABLE TEST PIT PERCOLATION GROUNDWATER DEPTH FROM PRESOAKED? DIAMETER OF DESCRIPTION RATE (MIN/IN) PRESENT (Y/N) GRADE (Y/N) HOLE TP-C14 10/26/2020 LIGHT BROWN SANDY SILT 24"

		DEEP HOLE	TESTING .	DATA TABL	E	
TEST PIT NO.	DATE TESTED	TEST PIT DESCRIPTION	DEPTH ACHEIVED	GROUNDWATER PRESENT (Y/N)	DEPTH TO ROCK	MOTTLIN (Y/N)
TP-C1	10/20/2020	0"-8" TOPSOIL 8"-96" LIGHT BROWN SANDY SILT	96"	NO	N/A	N
TP-C2	10/20/2020	0"-8" TOPSOIL 8"-96" LIGHT BROWN SANDY SILT	96"	NO	N/A	N
TP-C3	10/20/2020	0"-8" TOPSOIL 8"-96" LIGHT BROWN SANDY SILT	96"	NO	N/A	N
TP-C4	10/20/2020	0"-8" TOPSOIL 8"-96" LIGHT BROWN SANDY SILT	96"	NO	N/A	N
TP-C5	10/20/2020	0"-8" TOPSOIL 8"-96" LIGHT BROWN SANDY SILT	96"	NO	N/A	N
TP-C6	10/20/2020	0"-8" TOPSOIL 8"-96" LIGHT BROWN SANDY SILT	96"	NO	N/A	N
TP-C7	10/20/2020	0"-8" TOPSOIL 8"-96" LIGHT BROWN SANDY SILT	96"	NO	N/A	N
TP-C8	10/20/2020	0"-8" TOPSOIL 8"-96" LIGHT BROWN SANDY SILT	96"	NO	N/A	N

T SILI				
	MININAL HORIZ DISTANO	PONTAL S SES (IN F		RA TION
	EXISTING FEATURE	WATERTIGHT SEPTIC TANK	SEWER LINE	ABSORPTION FIELD
	DRILLED WELL-PUBLIC WATER SYSTEM	100	50	200
	WATER LINE (PRESSURE)	10	10	10
	STORMWATER INFILTRATION MANAGEMENT PRACTICE	25	25	50
	CATCH BASIN	25	N/A	50
	FOUNDATION	10	N/A	20
	PROPERTY LINE	10	10	10
	SWALE	N/A	N/A	25

	·
TEST LOG	CATION LABELS LEGEND
₩ В-Х	BORING LOCATION/DESIGNATION
TP−X	TEST PIT LOCATION/DESIGNATION
-∰- SW-X	STORMWATER TEST LOCATION/DESIGNATION
→ тР-СХ	CIVIL ENGINEER TEST PIT/INFILTRATION TEST LOCATION/DESIGNATION
TEST LOCATION LEG	SEND NOTES:

A. BORINGS, TEST PITS AND STORMWATER TESTS WERE PERFORMED BY CARLIN-SIMPSON AND ASSOCIATES. THE CIVIL ENGINEER TEST PITS/INFILTRATION TESTS WERE PERFORMED BY JMC, PLLC TO ACQUIRE INFORMATION FOR THE DESIGN OF THE PROPOSED ON SITE WASTEWATER TREATMENT SYSTEM.

	EXISTING EASEMENT LINE
	EXISTING WETLAND LINE AND DELINEATION
<u> </u>	EXISTING BUILDING LINE
	EXISTING PAVEMENT EDGE
	EXISTING CURB LINE
172	EXISTING CONTOUR
170_	EXISTING INDEX CONTOUR
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	EXISTING STONE WALL
	EXISTING RETAINING WALL
	EXISTING GUIDE RAIL
xxx	EXISTING FENCE
36" RCP	EXISTING STORM DRAIN LINE AND SIZE
	EXISTING SANITARY LINE AND SIZE
	EXISTING DRAIN INLET
0	EXISTING MANHOLE
	EXISTING FIRE HYDRANT
GV ⋈	EXISTING GAS VALVE
₩V	EXISTING WATER VALVE
-0-	EXISTING UTILITY POLE
☆	EXISTING LIGHT POLE
<del></del>	EXISTING SIGN
	PROPOSED BUILDING LINE

PROPOSED CONCRETE CURB

PROPOSED CONCRETE SIDEWALK

EXISTING PROPERTY LINE

● SMH	PROPOSED SANITARY SEWER MANHOLE	
● MH	PROPOSED STORM DRAIN MANHOLE	
CI	PROPOSED TYPE CI DRAIN INLET	
<b>■</b> DI	PROPOSED TYPE DI DRAIN INLET	
(	PROPOSED HEADWALL	
<b>€</b> wQS	PROPOSED WATER QUALITY STRUCTURE	
OCS	PROPOSED SUBSURFACE DRAINAGE OUTLET CONTROL STRUCTURE	
ocs	PROPOSED OUTLET CONTROL STRUCTURE	
● co	PROPOSED CLEANOUT	
•	PROPOSED HYDRANT	
15" HDPE	PROPOSED STORM DRAIN LINE & SIZE	
8" PVC	PROPOSED SANITARY SEWER LINE & SIZE	
6" WATER	PROPOSED WATER LINE & SIZE	
•	PROPOSED WATER VALVE	
	PROPOSED RETAINING WALL (DESIGN BY OTHERS)	

ALL STORMWATER MANAGEMENT PRACTICES SHALL REMAIN UNDISTURBED AND BE PROTECTED FROM HEAVY MACHINERY TRAFFIC DURING CONSTRUCTION. HOWEVER DURING CONSTRUCTION OF THE PRACTICE THE CONTRACTOR SHALL MINIMIZE AND AVOID HEAVY MACHINERY TRAFFIC TO THE MAXIMUM EXTENT PRACTICABLE. THERE SHALL BE NO STORAGE OF MATERIALS WITHIN AREAS TO BE USED FOR STORMWATER MANAGEMENT PRACTICES. THE CONTRACTOR SHALL INSTALL CONSTRUCTION FENCE AROUND THE PRACTICE TO DISCOURAGE VEHICLE TRAFFIC GEOTECHNICAL BORING/TEST PIT LOCATIONS DEPICTED ON THIS PLAN WERE TAKEN FROM THE GEOTECHNICAL REPORT ENTITLED, "REPORT ON SUBSURFACE SOIL AND FOUNDATION INVESTIGATION", DATED 10/14/2020, PREPARED BY CARLIN-SIMPSON AND ASSOCIATES, SUPPLEMENTED BY LOCATIONS OBSERVED BY JMC EMPLOYEES AND LOCATED USING GPS COORDINATES.

4. UNLESS OTHERWISE SPECIFIED, PIPE FOR STORM DRAINS SHALL BE HIGH DENSITY POLYETHYLENE PIPE (HDPE) WITH A SMOOTH INTERIOR AND ANNULAR EXTERIOR CORRUGATIONS IN ACCORDANCE WITH ASTM F-2648. JOINTS SHALL BE WATERTIGHT IN ACCORDANCE WITH ASTM D-3212.

5. UNLESS OTHERWISE SPECIFIED, PIPE FOR SANITARY SEWER GRAVITY LINES SHALL BE POLYVINYL CHLORIDE PIPE (PVCP), SDR-35, WITH PUSH-ON JOINTS IN ACCORDANCE WITH ASTM D-3034 AND D-3212. 6. UNLESS OTHERWISE SPECIFIED, PIPE FOR WATER LINES SHALL BE DOUBLE

CEMENT-LINED DUCTILE IRON PIPE (DIP), CLASS 52, WITH MECHANICAL JOINTS IN ACCORDANCE WITH AWWA C-150, C-151, C-104 AND C-111 7. ELECTRIC, TELEPHONE, FIRE ALARM AND CABLE TELEVISION LINES SHALL BE INSTALLED UNDERGROUND IN CONDUIT IN ACCORDANCE WITH THE REQUIREMENTS OF THE UTILITY COMPANY HAVING JURISDICTION.

8. REFER TO JMC DRAWING C-300 "UTILITIES PLAN" FOR THE CONTINUATION OF THE SANITARY SEWER.

# ORANGE COUNTY DEPARTMENT OF HEALTH NOTES:

1. APPLICANT: **FARRELL BUILDING COMPANY** PROPERTY OWNER: CHUN S. MCGLASSON SITE LOCATION: ROUTE 300, TOWN OF NEWBURGH, NY 12550

TAX MAP NUMBER OF PARCELS: SECTION 34 BLOCK 02 LOT 45 2. ELEVATIONS OF THE ON-SITE WASTEWATER TREATMENT SYSTEM HAVE BEEN ESTABLISHED BASED ON THE SEWER INVERT AT THE BUILDING LINE AND GROUND ELEVATIONS WITHIN THE ABSORPTION AREA. SHOULD THE SEWER INVERT BE CHANGED, ADJUSTMENTS OF ELEVATIONS TO THE REMAINING PORTIONS OF THE SYSTEM MAY BE REQUIRED. ALL CHANGES SHALL BE ENDORSED BY THE ENGINEER

3. THE DESIGN OF THE ON-SITE WASTEWATER TREATMENT AREAS ARE BASED ON A SOIL PERCOLATION RATE OF 21-30 MIN./INCH AND THE CONSTRUCTION OF TWO WAREHOUSES TOTALING 290,000 SQUARE FEET, BASED UPON ONE EMPLOYEE PER 1,000 SQUÁRE FEET AND 12 GPD/EMPLOYEE (15 GPD - 20% FOR WATER SAVING FIXTURES) A MAXIMUM FLOW RATE OF 3,480 GPD IS ANTICIPATED.

4. THE ON-SITE WASTEWATER TREATMENT SYSTEM FOR THE BUILDING SHALL INCLUDE THE FOLLOWING IMPROVEMENTS: __________ LINEAR FEET, 24 INCH WIDE ABSORPTION TRENCH (PRIMARY)

_2944 LINEAR FEET, 24 INCH WIDE ABSORPTION TRENCH (EXPANSION) 1-3,500 GALLON PRECAST CONCRETE SEPTIC TANK 1-2,000 GALLON PRECAST CONCRETE SEPTIC TANK

_____4 ___ EACH PRECAST CONCRETE 8 OUTLET DISTRIBUTION BOX ADDITIONAL IMPROVEMENTS: 4 OUTLET ALTERNATING CUE BOX DOSING CHAMBER

EFFECT AT THE TIME OF CONSTRUCTION WHICH INCLUDE:

5. THE DESIGN SDS TREATMENT CAPACITY IS 3,480 GALLONS PER DAY HANDLED WITH 24" WIDE ABSORPTION TRENCHES. IT IS BASED UPON NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION "NEW YORK STATE DESIGN STANDARDS FOR INTERMEDIATE SIZED WASTEWATER TREATMENT SYSTEMS", TABLE 3, EXPECTED LOADING RATES FOR A WAREHOUSE OF 15 GAL./DAY PER EMPLOYEE, AT 290 EMPLOYEES. THE SDS REQUIRED AREA IS 5,800 SQUARE FEET BASED UPON AN APPLICATION RATE OF 0.60 GAL/DAY/SF, 5,888 SQUARE FEET OF TREATMENT AREA IS PROVIDED.

6. BASE INFORMATION WAS TAKEN FROM THE "TOPOGRAPHIC SURVEY OF PROPERTY," PREPARED BY JMC, LAST REVISED 10/29/2020. 7. THE BUILDING SEWER PIPE SHALL BE LAID ON A FIRM FOUNDATION AT A MINIMUM GRADE OF ONE—QUARTER INCH PER FOOT (2.00%). NINETY DEGREE ELBOWS ARE NOT PERMITTED AND ALL FORTY FIVE DEGREE BENDS SHALL HAVE ACCESSIBLE CLEANOUTS.

8. ALL PIPES CONNECTING TO TANK AND BOXES SHALL BE CUT FLUSH WITH THE INSIDE WALL OF THE BOX. 9. PRIOR TO ANY EXCAVATION ALL UNDERGROUND UTILITIES MUST BE LOCATED. CALL 1-800-962-7962. 10. THE DESIGN, CONSTRUCTION AND INSTALLATION SHALL BE IN ACCORDANCE WITH THIS PLAN AND GENERALLY ACCEPTED STANDARDS IN

"RECOMMENDED STANDARDS FOR SEWAGE TREATMENT WORKS, (TEN STATES)." "NEW YORK STATE DEPARTMENT OF HEALTH AND ORANGE COUNTY DEPARTMENT OF HEALTH POLICIES, PROCEDURES AND

"NEW YORK STATE DESIGN STANDARDS FOR INTERMEDIATE SIZED WASTEWATER TREATMENT SYSTEMS"

11. THIS PLAN IS APPROVED AS MEETING THE APPROPRIATE AND APPLIED TECHNICAL STANDARDS, GUIDELINES, POLICIES AND PROCEDURES FOR ARRANGEMENT OF SEWAGE DISPOSAL AND TREATMENT AND WATER SUPPLY FACILITIES.

12. THE DESIGN AND LOCATION OF SANITARY FACILITIES (WATER AND SEWER SYSTEMS) SHALL NOT BE CHANGED.

13. NO WELLS EXIST WITHIN 300 FT OF THIS PROJECT UNLESS SHOWN ON THE PLANS.

14. TRENCHES SHALL NOT BE INSTALLED IN WET SOIL. THE SIDE AND BOTTOM OF TRENCHES MUST BE RAKES. THE ENDS OF LATERALS 15. THERE IS NO REGRADING EXCEPT AS SHOWN ON THE APPROVED PLANS, IN THE AREA OF THE ABSORPTION FIELDS

16. HEAVY EQUIPMENT SHALL BE KEPT OFF THE AREA OF THE ABSORPTION FIELDS EXCEPT DURING THE ACTUAL CONSTRUCTION. THERE SHALL BE NO UNNECESSARY MOVEMENT OF CONSTRUCTION EQUIPMENT IN THE ACTUAL ABSORPTION FIELD AREA, BEFORE, DURING OR AFTER CONSTRUCTION. EXTREME CARE MUST BE TAKEN DURING THE ACTUAL CONSTRUCTION SO AS TO AVOID ANY UNDUE

17. NO SWIMMING POOLS, DRIVEWAYS OR STRUCTURES THAT MAY COMPACT THE SOIL SHALL BE LOCATED OVER ANY PORTION OF THE

COMPACTION THAT COULD RESULT IN A CHANGE OF THE ABSORPTION CAPACITY OF THE SOIL ON WHICH THE DESIGN WAS BASED.

18. THIS SYSTEM WAS NOT DESIGNED TO ACCOMMODATE GARBAGE GRINDER, JACUZZI TYPE SPA TUBS OVER 100 GALLONS, OR WATER CONDITIONERS. AS SUCH THESE ITEMS SHALL NOT BE INSTALLED UNLESS THE SYSTEM IS REDESIGNED TO ACCOUNT FOR THEM AND REAPPROVED BY THE ORANGE COUNTY HEALTH DEPARTMENT.

19. THERE MUST BE AN UNINTERRUPTED POSITIVE SLOPE FROM THE SEPTIC TANK (OR ANY PUMPING OR DOSING CHAMBERO TO THE BUILDING, ALLOWING SEPTIC GASES TO DISCHARGE THROUGH THE STACK VENT.

20. THE OWNER APPLICANT SHALL BE PROVIDED WITH A COPY OF THE APPROVED PLANS AND AN ACCURATE AS-BUILT DRAWING OF ANY

EXISTING SANITARY FACILITIES. 21. THE SEPTIC TANKS SHOULD BE INSPECTED PERIODICALLY AND PUMPED EVERY 2-3 YEARS.

22. DISTRIBUTION BOX SHOULD BE INSPECTED PERIODICALLY TO ASSURE THAT THEY ARE LEVEL AND OPERATING PROPERLY.

23. INDIVIDUAL SEWAGE DISPOSAL SYSTEMS SHALL NO LONGER BE CONSTRUCTED OR USED WHEN PUBLIC FACILITIES BECOME AVAILABLE. CONNECTION TO THE PUBLIC SEWER SYSTEM IS REQUIRED WITHIN ONE YEAR OF AVAILABILITY. 24. ORANGE COUNTY DEPARTMENT OF HEALTH PLAN APPROVAL IS LIMITED TO 5 YEARS. TIME EXTENSIONS FOR PLAN APPROVAL MAY BE GRANTED BY THE ORANGE COUNTY DEPARTMENT OF HEALTH BASED UPON REGULATIONS IN EFFECT AT THAT TIME. A NEW PLAN

SUBMISSION MAY BE REQUIRED TO OBTAIN A TIME EXTENSION. 25. A NEW YORK STATE LICENSED PROFESSIONAL ENGINEER SHALL INSPECT THE SANITARY FACILITIES AT THE TIME OF CONSTRUCTION.
THE ENGINEER SHALL CERTIFY TO THE ORANGE COUNTY DEPARTMENT OF HEALTH AND THE LOCAL CODE ENFORCEMENT OFFICER THAT
THE FACILITIES HAVE BEEN INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND THAT ANY SEPTIC TANK JOINTS HAVE BEEN SEEALED AND TESTED FOR WATER TIGHTNESS.

ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.

12/03/2020 Project No: 18156 18156-SEPTIC OWTS GRADUTIL.scr C - 310

SITE PLAN

1" = 80'

OWTS DETAIL PLAN

1" = 30'



ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW,


Scale: 1" = 50'

Project No: 18156 18156-S&E SE.scr




ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND


REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.




FIRE TRUCK -ENTERING AND EXITING-



DELIVERY TRUCK -EXITING-



<u>DELIVERY TRUCK</u> -ENTERING-




DELIVERY TRUCK


-EXITING ALT-


Drawn: TC Approved: DL/JS
Scale: 1" = 100' Date: 12/03/2020
Project No: 18156


ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.


TURNING






















ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.

12/03/2020 18156-LAND | L-100 | LAND.scr

