

MICHAEL J. LAMOREAUX, P.E. (NY, NJ, PA, VT, VA & CT) MICHAEL W. WEEKS, P.E. (NY, NJ & PA) LYLE R. SHUTE, P.E., LEED-AP (NY, NJ, PA) PATRICK J. HINES Main Office 33 Airport Center Drive Suite 202 New Windsor, New York 12553

(845) 567-3100 fax: (845) 567-3232 e-mail: <u>mheny@mhepc.com</u>

Principal Emeritus: RICHARD D. McGOEY, P.E. (NY & PA)

TOWN OF NEWBURGH PLANNING BOARD TECHNICAL REVIEW COMMENTS

PROJECT:	CHADWICK WOODS SUBDIVISION
PROJECT NO.:	19-02
PROJECT LOCATION:	SECTION 14, BLOCK 1, LOT 51
REVIEW DATE:	14 MAY 2021
MEETING DATE:	20 MAY 2021
PROJECT REPRESENTATIVE:	TALCOTT ENGINEERING/CHARLES BROWN

- **1.** NYSDOT approval of the private road access and single driveway to the State highway is required.
- 2. In response to a previous comment, the applicant has identified a flow and pressure analysis for the proposed Lot #4 ,furthest from the Town watermain. The response identifies that 1 ¼-inch line has been proposed to this residence. This is not a standard size readily available. We are suggested 1 ½-inch might be utilized which is more readily available for any required repairs. The water and sewer department has allowed the use of HDPE pipe on these long runs for residential service. An approval must be received from the Water Department prior to installation of the alternative pipe.
- **3.** Additional notes updated for the Town of Newburgh should be added to the water plans. Copy of the current standard water notes have been added, any missing from the plans should be added.
- **4.** Reference to booster pump stations Note #11 Sheet 6 of 7 should be removed from the plans.
- **5.** The restrained joint pipe chart must be added the plans. Current water details identify thrust blocks. Thrust blocks are not permitted for the Town of Newburgh system.
- **6.** Tapping valve and sleeve should be identified for connection to the Town's watermain for the watermain extension.
- **7.** Health Department approval for watermain extension with hydrants is required. The Planning Board may wish to authorize this office to prepare a letter allowing submission to the Health Department.
 - Regional Office 111 Wheatfield Drive Suite 1 Milford, Pennsylvania 18337 570-296-2765 •



8. Sheet 1of 7 does not identify a building envelope on Lot #5.

Respectfully submitted,

McGoey, Hauser and Edsall Consulting Engineers, D.P.C.

when & Afenes

Patrick J. Hines Principal

PJH/dns

Talcott Engineering DESIGN, PLLC

1 GARDNERTOWN ROAD ~ NEWBURGH, NY 12550 (845) 569-8400* ~ (fax) (845) 569-4583

May 14, 2021

Mr. John Ewasutyn, Chairman Town of Newburgh Planning Board 308 Gardnertown Road Newburgh, NY 12550

Re: Resubmission Letter Chadwick Woods Subdivision Town Project No. 2019-02 NYS Route 300 SBL: 14-1-51 Job No. 17100-MMR

Dear John,

The following is my response to comments from Pat Hines and the Planning Board from the August 6, 2020, Planning Board meeting;

1) (No response necessary)

2) Topography on NYS Route 300, for the proposed private road, and driveway entrances is updated based on field survey by the project surveyor and proposed grading has been revised accordingly. Plans have sufficient detail for DOT submission.

3) The requested profile has been added to plans. We are prepared to submit the water main to the Health Department.

4, 5, 6) The existing 12" water main has been located on the plans and labeled 12" with 70 PSI pressure. (sheet 1). Based on my analysis of the Lot 4 with a 1" service line, at 5 GPM, pressure at the residence was 40 PSI, I therefore upsized this service line to $1 \frac{1}{4}$ ".

7) New 6" water main will be ductile iron.

8) Pipe joist restraints have been added to the plans.

9) The hydrant is new. Gate valves are all shown. The Water Department has not yet provided details.

10) Hydrant drain is just below ground surface and above ground water, based on depth tests.

11) The Water Department will not review plans at this time.

12) Booster pumps are no longer proposed.

13) An easement on Lot 3 for Lot 4 water service is now shown.

14) Will be addressed by applicants attorney.

15) Changed as requested.

16) Building envelopes are shown on sheet 1.

17) See 9) above.


18) The SWPPP is currently being generated.


Attached please find 12 sets of plans, I have delivered one set to Pat Hines, one set to Dominic Cordisco, and FedExed one set to Ken Wersted.

Respectfully yours,

Charles T. Brown, P.E. – President Talcott Engineering

Pc; Mike Maher, Developer /Pat Hines W/plans Dominic Cordisco, Esq. w/plans Ken Wersted w/plans





now or formally Duff 14-1-53.4(well) now or formally Rossi 14-1-53.31(town water) CLEARING AREA (TYP.)_ -<u>LOT #1</u> -2.06AC now or form ALEX 14–1–29 FS paved drive PROPOSED 12" CULVERT CONECTED TO EXSTING BURIED WELL LQCATHO now or formally SCOTT 14-1-52 now or formall LOWES 14–1–31 ISTING " culvert STABIL CONSTROPOSED; 6" WATER ENTRANDCFO CONNECT TO EXISTING 12" MAIN WITH 12"x6" TAPPING SLEEVE AD X P11 SUTLITY POLE TO GATE VALVE IN •D11 ACCORDANCE WITH WATER L PROPOSED 15"HDPE DEPARTMENT CULVERT REQUIREMENTS. now or formally LENT 14-1-32 EXISTING - 12" WATER MAIN now or formally 70PSI± MAINES 14-1-33 TOWN OF NEWBURGH CERTIFICATION: KA90 "I HEREBY CERTIFY TO THE TOWN OF NEWBURGH THAT THE SEWERAGE SYSTEM DEPICTED ON THIS PLAT HAS BEEN DESIGNED IN ACCORDANCE WITH THE NEW YORK STATE PUBLIC HEALTH LAW AND ALL REGULATIONS PROMULGATED THEREUNDER." TOWN PROJECT # 2019-02 THIS SHEET IS INVALID AND VOID UNLESS ACCOMPANIED BY REMAINING SHEETS IN SET. TALCOTT ENGINEERING DESIGN PLLC ENGINEER 1 GARDNERTOWN ROAD NEWBURGH, NY 12550 (845)–569–8400 (FAX)(845)–569–4583 TALCOTTDESIGN12@GMAIL.COM PROPOSED LAYOUT & GRADING PROPOSED SUBDIVISION ENTITLED CHADWICK WOODS ROUTE 300, SBL 14-1-51 TOWN OF NEWBURGH, ORANGE COUNTY, NY JOB NUMBER SHEET NUMBER DATE SCALE 17100- MMR 1" = 40' 2 OF 7 CHARLES T. BROWN, P.E. 01/09/19

<u>LOT #</u>	<u>LOT 1</u>	<u>LOT 2</u>
	D1 60" DEEP 04/24/17 0-6" TOP SOIL 6"-28" CLAY LOAM W/GRAVEL 28"-60" CLAY LOAM W/GRAVEL "DAMP" NO ROCK, WATER, OR MOTTLING	D11 72" DEEP 04/24/17 0-6" TOP SOIL 6"-72" CLAY LOAM NO ROCK, WATER @ 50", NO MOTTLING
	● <u>D2</u> 78" DEEP 04/24/17 0-6" TOP SOIL 6-32" CLAY LOAM 32-78" CLAY LOAM "DAMP" NO ROCK, WATER, OR MOTTLING	 ● D12 72" DEEP 04/24/17 0-6" TOP SOIL 6"-72" CLAY LOAM NO ROCK, WATER @ BOTTOM, MOTTLING ● D13 30" DEEP 07/01/19
<u>DEEP TEST DATA:</u>	● <u>D3</u> 88" DEEP 04/24/17 0-6" TOP SOIL 6"-55" CLAY LOAM 55"-88" CLAY LOAM "DAMP" NO ROCK, NO WATER, MOTTLING @ 55"	0–6" TOP SOIL 6"–30" CLAY LOAM NO ROCK, WATER @ BOTTOM, NO MOTTL
	* P1 15" DEEP 04/24/17 1 2 3 FINISH 3:55 4:22 4:50 START 3:11 3:55 4:23 TIME :24 :27 :27 STABILIZED PERCOLATION RATE: 27 MINUTES /INCH	★ P11 12" DEEP 11/08/17 1 2 3 FINISH 2:39 3:45 4:51 START 1:52 2:39 3:45 TIME :47 :66 :66 STABILIZED PERCOLATION RATE: 66 MINUTES /INCH
	* P2A 12" DEEP 06/15/17 1 2 3 4 5 FINISH 2:20 2:38 3:20 4:05 4:09 START 2:12 2:21 2:39 3:22 4:06 TIME :08 :17 :41 :43 :43 STABILIZED PERCOLATION RATE: 43 MINUTES / INCH	* P12 12" DEEP 11/08/17 1 2 3 FINISH 1:45 3:40 4:40 START 2:40 2:40 3:40 TIME :55 :60 :60 STABILIZED PERCOLATION RATE: 60 MINUTES /INCH
PERCOLATION DATA:	* P2B 24" DEEP 06/15/17 1 2 3 4 5 FINISH 1:10 1:47 2:32 3:29 4:49 START 12:52 1:11 1:48 2:35 3:30 TIME :18 :36 :44 :54 :54 STABILIZED PERCOLATION RATE: 54 MINUTES / INCH * P3A 12" DEEP 06/15/17	* P17 12" DEEP 07/03/18 1 2 3 FINISH 3:41 3:47 3:54 START 3:39 3:41 3:48 TIME :02 :06 :06 STABILIZED PERCOLATION RATE: 6 MINUTES /INCH
	1 2 3 FINISH 2:21 2:30 2:39 START 2:14 2:22 2:31 TIME :07 :08 :08 STABILIZED PERCOLATION RATE: 8 MINUTES /INCH * <u>P3B</u> 24" DEEP 06/15/17	* P19 12" DEEP 07/01/19 1 2 3 FINISH 3:02 3:17 3:32 START 2:49 3:03 3:18 TIME :13 :14 :14 STABILIZED PERCOLATION RATE: 14 MINUTES /INCH
	1 2 3 4 3 FINISH 1:24 2:03 2:44 3:27 4:18 START 12:55 1:25 2:04 2:38 3:29 TIME :29 :38 :40 :49 :49 STABILIZED PERCOLATION RATE: 49 MINUTES /INCH	
	* <u>*USED FOR DESIGN</u>	** <u>USED_FOR_DESIGN</u>
<u>SEPTIC DESIGN CRITERIA:</u>	1. NO. OF BEDROOMS- 4 2. SEPTIC TANK DESIGN-1,250 GAL 3. STABILIZED PERCOLATION RATE- 45-60 MIN 4. FLOW RATE (GALS /DAY)- 440 5. DESIGN LENGTHS: 4 ROWS OF 11 ELJEN UNITS(44'ROWs) = 44 units total((41units REQ'D) * 6. SHALLOW FILL SYSTEM(18") 7. CURTAIN DRAIN REQUIRED	 NO. OF BEDROOMS – 4 SEPTIC TANK DESIGN – 1,250 GAL STABILIZED PERCOLATION RATE – 31–45 MIN FLOW RATE (GALS /DAY) – 440 DESIGN LENGTHS: 4 ROWS OF 10 ELJEN UNITS(40'ROWs) = 40 units total((37units REQ'D) * 6. SHALLOW FILL SYSTEM(18") 7. CURTAIN DRAIN REQUIRED
 200 FEET UP SLOPE AND 2. SEPTIC TANK TO BE LOCA ANY BUILDING OR PROPE 3. CELLAR DRAINS, ROOF DI DISCHARGED IN OR INTO 4. NO SWIMMING POOLS, DR SHALL BE CONSTRUCTED 5. NO TRENCHES TO BE INS 6. RAKE SIDES AND BOTTOM ABSORPTION TRENCH. 7. GROUT ALL PIPE PENETR. 8. DISTRIBUTION LINES ARE 9. THE PERIMETER OF THE SURFACE WATER. 10. ALL NEWLY DISTURBED AND 	RAINS OR FOOTING DRAINS SHALL NOT BE THE VICINITY OF ABSORPTION FIELD. RIVEWAYS, OR STRUCTURES THAT MAY COMPACT THE SOIL OVER ANY PORTION OF THE ABSORPTION FIELD. STALLED IN WET SOIL. I OF TRENCH PRIOR TO PLACING GRAVEL IN ATIONS TO CONC. SEPTIC TANK & DISTRIBUTION BOX.	 NOTES: BENDS SHALL BE USED WHEN ENTRANCE OR EX NOT APPROXIMATELY STRAIGHT. IF BENDS ARE U THAN ENTRANCE OR EXIT POINTS, THEN A CLEAR OF ANGED WITHOUT RESUBMISSION FOR APPROVAL CHANGED WITHOUT RESUBMISSION FOR APPROVAL HEAVY EQUIPMENT SHALL BE KEPT OFF THE ARE FIELDS EXCEPT DURING THE ACTUAL CONSTRUCTION ABSORPTION FIELD AREA BEFORE, DURING, OR A THIS SYSTEM WAS NOT DESIGNED TO ACCOMMODI JACUZZI TYPE SPA TUBS OVER 100 GALLONS, O AS SUCH, THESE ITEMS SHALL NOT BE INSTALLE IS REDESIGNED TO ACCOUNT FOR THESE. THERE MUST BE AN UNINTERRUPTED POSITIVE SL TANK (OR ANY PUMPING OR DOSING CHAMBER) SEPTIC GASES TO DISCHARGE THROUGH THE ST 18. THE PURCHASER OF THIS LOT SHALL BE PROVID

OR 35' DRAINAGE DITCH.

SYSTEM.


11. NO SEWAGE SYSTEM SHALL BE PLACED WITHIN 100' OF ANY WATER COURSE

12. ALL LAUNDRY AND KITCHEN WASTES SHALL BE DISCHARGED INTO SEWAGE


- SEPTIC GASES TO DISCHARGE THROUGH THE STACK VENT. 18. THE PURCHASER OF THIS LOT SHALL BE PROVIDED WITH A COPY OF THE APPROVED PLANS AND AN ACCURATE AS-BUILT DRAWING OF ANY EXISTING
- SANITARY FACILITIES. 19. THE DESIGN ENGINEER WILL BE REQUIRED TO CERTIFY THE COMPLETED DISPOSAL FACILITY. 20. AN ASBUILT SURVEY AND CERTIFICATION SHALL BE PROVIDED TO THE TOWN OF NEWBURGH CODE ENFORCEMENT DEPARTMENT PRIOR TO ISSUANCE .OF A CERTIFICATION OF OCCUPANCY.


<u>LOT 3</u> <u>LOT 4</u> <u>LOT 5</u> 84" DEEP • D10 🗣 D4 30" DEEP •<u>D41</u> 72" DEEP •<u>D9</u> 04/24/17 07/01/19 04/24/17 60" DEEP 04/24/17 0-6" TOP SOIL TOP SOIL 0-6" TOP SOIL 0-6" 6"-42" CLAY LOAM TOP SOIL 6"-60" CLAY LOAM W/STONES 6"-30" CLAY LOAM 6"-24" CLAY LOAM W/GRAVEL 42"-84" CLAY LOAM W/SMALL STONES "DAMP" ING NO ROCK, WATER @ 40", NO MOTTLING NO ROCK, WATER, OR MOTTLING 24"-72" CLAY LOAM NO ROCK, WATER, OR MOTTLING NO ROCK, WATER SEEAGE @ 30" 🕒 D8 *60" DEEP 04/24/17* 17 60" DEEP 04/24/17 • D5 0-6" • D42 TOP SOIL 72" DEEP 04/24/17 TOP SOIL 0-6" 6"-60" WET CLAY LOAM 6"-60" CLAY LOAM 0-6" TOP SOIL NO ROCK, WATER @ 28", MOTTLING @ 28" LING @ 46" NO ROCK, WATER @ 12", MOTTLING @ 12" 6"-24" CLAY LOAM W/GRAVEL 24"-72" CLAY LOAM • D14 30" DEEP 04/24/17 NO ROCK, WATER SEEAGE @ 30" ●<u>___6</u> 60" DEEP 0-6" 4/24/17 19 TOP SOIL TOP SOIL 6"-30" CLAY LOAM 6-40" CLAY LOAM NO ROCK, WATER, OR MOTTLING 40-60" WET CLAY LOAM W/GRAVEL OTTLING NO ROCK, WATER @ 40", MOTTLING @ 40" • D7 60" DEEP 4/24/17 0-12" TOP SOIL 12–60" WET CLAY LOAM NO ROCK, WATER @ 24", MOTTLING @ 24" * P13 12" DEEP 07/03/18 16" DEEP 06/15/17 *12" DEEP 11/08/17* * P4 * P10 07/20/17 * P8 12" DEEP - 2 11:26 1:05 1:50 :45 FINISH 11:30 11:35 1:57 4:07 FINISH 3:42 4:10 4:40 FINISH 12:34 12:44 FINISH 3:12 12:41 4:13 START 11:26 11:31 2:57 3:07 3:57 START 3:43 11:24 3:29 START 11:40 1:40 START 1:03 TIME TIME :13 :27 :27 :02 :04 :04 :60 :60 TIME :22 :45 TIME :54 :56 11 STABILIZED PERCOLATION RATE: 27 MINUTES /INCH STABILIZED PERCOLATION RATE: 4 MINUTES /INCH STABILIZED PERCOLATION RATE: 60 MINUTES /INCH STABILIZED PERCOLATION RATE: 45 MINUTES /INCH *12" DEEP 06/16/17* * P14 12" DEEP 07/03/18 * P5 3:05 3:53 4:40 FINISH 2:27 12:30 12:57 * <u>P41</u> 12" DEEP 12/20/18 FINISH 12:02 07/120/17 12" DEEP * <u>P9</u> 3:08 :45 START 2:30 3:55 2:20 12:31 START 11:51 12:04 TIME :07 :35 :45 :11 TIME :26 :26 2:29 1:32 FINISH 3:27 FINISH 12:57 1:48 2:39 1:31 12:05 STABILIZED PERCOLATION RATE: 45 MINUTES /INCH STABILIZED PERCOLATION RATE: 26 MINUTES /INCH START 2:30 12:48 12:47 12:11 1:49 START 11:30 TIME :57 :57 TIME :50 :50 :44 :35 :46 CH STABILIZED PERCOLATION RATE: 57 MINUTES /INCH STABILIZED PERCOLATION RATE: 50 MINUTES /INCH * P15 12" DEEP 07/03/18 * <u>P6</u> *12" DEEP 06/16/18* FINISH 1:35 1:49 2:02 12:40 1:30 07/03/18 2:18 START FINISH 1:24 12" DEEP 1:37 1:50 * <u>P16</u> 12" DEEP * <u>P42</u> 12/20/18 START 12:43 1:31 TIME :11 12:20 :12 :12 :47 :47 TIME :20 STABILIZED PERCOLATION RATE: 12 MINUTES /INCH 2:44 2:53 FINISH 2:36 4 STABILIZED PERCOLATION RATE: 47 MINUTES /INCH 2:37 :07 START 2:46 2:33 1:38 1:21 :17 2:02 2:49 FINISH 1:20 1:12 TIME :03 :07 1:38 2:14 1:05 :07 START 1:12 STABILIZED PERCOLATION RATE: 7 MINUTES /INCH :24 :25 12" DEEP 07/01/19 TIME 12" DEEP 06/16/18 * P7 * <u>P18</u> :08 STABILIZED PERCOLATION RATE: 25 MINUTES /INCH 11:21 12:15 FINISH 3:00 3:17 3:34 FINISH 10:28 START 2:45 3:01 11:25 3:18 START 10:17 10:29 :50 TIME :15 TIME :11 :50 :16 :16 STABILIZED PERCOLATION RATE: 50 MINUTES /INCH STABILIZED PERCOLATION RATE: 16 MINUTES /INCH **USED_FOR_DESIGN **USED FOR DESIGN **USED FOR DESIGN 1. NO. OF BEDROOMS- 4 1. NO. OF BEDROOMS- 4 1. NO. OF BEDROOMS- 4 2. SEPTIC TANK DESIGN-1,250 GAL 2. SEPTIC TANK DESIGN-1,250 GAL 2. SEPTIC TANK DESIGN-1,250 GAL MIN 3. STABILIZED PERCOLATION RATE - 45-60 MIN 3. STABILIZED PERCOLATION RATE - 46-60 MIN 3. STABILIZED PERCOLATION RATE - 46-60 MIN 4. FLOW RATE (GALS /DAY)- 440 4. FLOW RATE (GALS /DAY)- 440 4. FLOW RATE (GALS /DAY)- 440 5. DESIGN LENGTHS: 5. DESIGN LENGTHS: 5. DESIGN LENGTHS: 4 ROWS OF 11 ELJEN UNITS(44'ROWs) 4 ROWS OF 11 ELJEN UNITS(44'ROWs) 4 ROWS OF 11 ELJEN UNITS(44'ROWS) = 44 units total((41units REQ'D) * = 44 units total((41units REQ'D) * = 44 units total((41units REQ'D) * 6. SHALLOW FILL SYSTEM 6. SHALLOW FILL SYSTEM (18") 6. SHALLOW FILL SYSTEM(18") 7. CURTAIN DRAIN REQUIRED 7. CURTAIN DRAIN REQUIRED 7. CURTAIN DRAIN REQUIRED 8. RESERVE AREA REQUIRED PUMP CHAMBER 8.PUMP CHAMBER REQUIRED STANDARD NOTES: EXIT FROM SEPTIC TANK IS THE DESIGN, CONSTRUCTION AND INSTALLATION SHALL BE IN ACCORDANCE RE USED AT POINTS OTHER WITH THIS PLAN AND GENERALLY ACCEPTED STANDARDS IN EFFECT AT THE TIME LEANOUT IS REQUIRED. OF CONSTRUCTION WHICH INCLUDE: FACILITIES SHALL NOT BE OVAL. "APPENDIX 75-A, WASTE TREATMENT - INDIVIDUAL HOUSEHOLD SYSTEMS, NEW YORK STATE SANITARY CODE. AREA OF THE ABSORPTION "WASTE TREATMENT HANDBOOK, INDIVIDUAL HOUSEHOLD SYSTEMS, NEW YORK RUCTION. THERE SHALL BE STATE DEPARTMENT OF HEALTH. TION EQUIPMENT IN THE "RURAL WATER SUPPLY, NEW YORK STATE DEPARTMENT OF HEALTH." OR AFTER CONSTRUCTION. "PLANNING THE SUBDIVISION AS PART OF THE TOTAL ENVIRONMENT, NEW MODATE GARBAGE GRINDERS, YORK STATE DEPARTMENT OF HEALTH." IS, OR WATER CONDITIONERS. TALLED UNLESS THE SYSTEM "THIS PLAN IS APPROVED AS MEETING THE APPROPRIATE AND APPLIED TECHNICAL STANDARDS, GUIDELINES, POLICIES AND PROCEDURES FOR ARRANGEMENT OF SEWAGE SLOPE FROM THE SEPTIC * SEWAGE DISPOSAL SYSTEMS MUST BE CONSTRUCTED USING DISPOSAL AND TREATMENT AND WATER SUPPLY FACILITIES. ER) TO THE HOUSE. ALLOWING THE "ELJEN B43 GSF TRENCH" AS MANUFACTURED BY ELJEN SYSTEMS. SEE ELJEN SYSTEMS NOTES AND DETAILS ON SHEET 4 ALL WELLS AND S.D.S. EXISTING OR APPROVED WITHIN 200' OF THE PROPOSED WELLS AND S.D.S. ARE SHOWN ON THIS PLAN ALONG WITH ANY OTHER ENVIRONMENTAL HAZARDS IN THE AREA THAT MAY AFFECT THE DESIGN AND FUNCTIONAL ABILITY OF THE S.D.S. AND WELL. IT SHALL BE DEMONSTRATED BY THE CONTRACTOR TO THE CERTIFYING THIS SHEET IS INVALID AND VOID UNLESS ACCOMPANIED BY REMAINING SHEETS IN SET. ENGINEER THAT THE SEPTIC TANK IS SEALED, WATER TIGHT AND ACCEPTABLE FOR USE. THIS SHALL REQUIRE, AS A MINIMUM, THE FILLING OF THE TANK WITH WATER TO TALCOTT ENGINEERING DESIGN PLLC ENGINEER OBSERVE IF IT IS IN FACT SEALED, WATERTIGHT AND ACCEPTABLE FOR USE. 1 GARDNERTOWN ROAD ALL PROPOSED WELLS AND SERVICE LINES ON THIS PLAN ARE ACCESSIBLE FOR NEWBURGH, NY 12550 INSTALLATION AND PLACEMENT. (845)–569–8400 (FAX)(845)–569–4583 TRENCH BOTTOMS TO BE SET LEVEL AND PARALLEL TO EXISTING CONTOURS. TALCOTTDESIGN12@GMAIL.COM MAXIMUM DEPTH OF USABLE FILL PLUS 6" OF TOPSOIL SHALL NOT EXCEED 30". SEPTIC DESIGN & TESTING PROPOSED SUBDIVISION ENTITLED CHADWICK WOODS ROUTE 300, SBL 14-1-51 TOWN OF NEWBURGH, ORANGE COUNTY, NY ARD PB COMMENTS ARD PB COMMENTS SCALE JOB NUMBER SHEET NUMBER CHARLES T. BROWN, P.E. 17100- MMR 01/11/19 N.T.S. 3 OF 7 ARD PB COMMENTS

RE	VISIONS		
REV.:	DATE:	BY:	DESCRIPTION:
3	05/21/21	RBM	REVISED PER BOA
 2	03/12/21	RBM	REVISED PER BOA
1	06/18/20	RBM	REVISED PER BOA



- CONSTRUCTION SCHEDULE FOR EACH LOT
- 1. OBTAIN PLAN APPROVAL AND OTHER APPLICABLE PERMITS. 2. FLAG THE WORK LIMITS
- 3. HOLD PRE-CONSTRUCTION CONFERENCE AT LEAST ONE WEEK PRIOR TO STARTING CONSTRUCTION.
- 4. INSTALL TEMPORARY GRAVEL CONSTRUCTION ENTRANCE/EXIT.
- 5. INSTALL SILT FENCE 6. COMPLETE SITE CLEARING
- 7. ROUGH GRADE SITE, STOCKPILE TOPSOIL, INSTALL DRIVEWAY CULVERT
- 8. EXCAVATE FOR FOUNDATION 9. BUILD FOUNDATION
- 10. FRAME HOUSE
- 11. BACKFILL FOUNDATION
- 12. FINISH THE SLOPES AROUND BUILDINGS AS SOON AS ROUGH GRADING IS COMPLETE. LEAVE THE SURFACE SLIGHTLY
- ROUGHENED AND VEGETATE AND MULCH IMMEDIATELY. 13. COMPLETE FINAL GRADING FOR DRIVEWAY AND BUILDING.
- 14. AFTER THE SITE IS STABILIZED, REMOVE ALL TEMPORARY MEASURES AND INSTALL PERMANENT VEGETATION ON THE DISTURBED AREAS.
- 15. ESTIMATED TIME BEFORE FINAL STABILIZATION--9 MONTHS.





VEGETATION REQUIREMENTS

1.) SITE PREPARATION

A. INSTALL NEEDED WATER AND EROSION CONTROL MEASURES AND BRING AREA TO BE SEEDED TO DESIRED GRADES USING A MINIMUM OF 4 IN. TOPSOIL. B. PREPARE SEEDBED BY LOOSENING SOIL TO A DEPTH OF 4-6 INCHES.

C. LIME TO A PH OF 6.5

E. FERTILIZE AS PER SOIL TEST OR, IF FERTILIZER MUST BE APPLIED BEFORE SOIL TEST RESULTS ARE RECEIVED, APPLY 850 POUNDS OF 5-10-10 OR EQUIVALENT

PER ACRE (20 LBS/1,000 SQ. FT.)

F. INCORPORATE LIME AND FERTILIZER IN TOP 2-4 INCHES OF TOPSOIL. G. SMOOTH. REMOVE ALL STONES OVER 1 INCH IN DIAMETER, STICKS, AND FOREIGN MATTER FROM THE SURFACE. FIRM THE SEEDBED.

2.) PLANTING--SUNNY LOCATION.

USE A CULTIPACKER TYPE SEEDER IF POSSIBLE. SEED TO A DEPTH OF 1/8 TO 1/4 INCH. IF SEED IS TO BE BROADCAST, CULTIPACK OR ROLL AFTER SEEDING. IF


HYDROSEEDED, LIME AND FERTILIZER MAY BE APPLIED THROUGH THE SEEDER AND ROLLING IS NOT PRACTICAL. SEED USING THE FOLLOWING MIX AND RATES


	00400	OFFOUND	ALL DT
			(UNDI
	GNAJJ	SEEDING	UNANT


SPECIES (% BY WEIGHT)	LBS./1,000SQ.FT	LBS./ACRE
65% KENTUCKY BLUEGRASS BLEND	2.0-2.6	85-114
20% PERENNIAL RYEGRASS	0.6–0.8	26–35
15% FINE FENSCUE	0.4-0.6	19-26
	3.0-4.0	130–175
100% TALL FENSCUE, TURF-TYPE, FINE LEAF	3.4-4.6	150–200

3.) WHEN USING THE CULTIPACKER OR BROADCAST SEED METHOD, MULCH USING SMALL GRAIN STRAW, APPLIED AT A RATE OF 2 TÓNS PER ACRE; AND ANCHOR WITH A NETTING OR TACKIFIER. HYDROSEED APPLICATIONS SHOULD INCLUDE MULCH, FERTILIZER AND SEED.

THE DRY SUMMER PERIOD. HOWEVER, THEY WILL NOT WITHSTAND HEAVY TRAFFIC. FERTILIZING—FIRST YEAR, (SPRING SEEDLINGS) THREE TO FOUR WEEKS AFTER GERMINATION APPLY 1 POUND NITROGEN/1,000 SQUARE FEET USING A COMPLETE FERTILIZER WITH A 2-1-1 OR 4-1-3 RATIO OR AS RECOMMENDED BY SOIL TEST RESULTS. FOR SUMMER AND EARLY FALL SEEDINGS, APPLY AS ABOVE UNLESS AIR TEMPERATURES ARE ABOVE 85°F FOR EXTENDED PERIOD. WAIT UNTIL HEAT WAVE IS OVER TO FERTILIZE. FOR LATE FALL/ WINTER SEEDINGS, FERTILIZE IN SPRING. RESTRICT USE—NEW SEEDLINGS SHOULD BE PROTECTED FROM USE FOR ONE FULL YEAR TO ALLOW DEVELOPMENT OF A DENSE SOD WITH GOOD ROOT STRUCTURE







RE	VISIONS		
V.:	DATE:	BY:	DESCRIPTION:
2	05/21/21	RBM	REVISED PER BO
1	06/08/20	RBM	REVISED PER BO

TOWN OF NEWBURGH (T.O.N.) WATER SERVICE NOTES

1. "CONSTRUCTION OF POTABLE WATER UTILITIES AND CONNECTION TO THE T.O.N. WATER SYSTEM REQUIRES A PERMIT FROM THE T.O.N. WATER DEPARTMENT. ALL WORK AND MATERIALS SHALL CONFORM TO THE REQUIREMENTS OF THE NYSDOH AND THE T.O.N."

2. ALL WATER SERVICE LINES FOUR (4) INCHES AND LARGER IN DIAMETER SHALL BE CEMENT LINED CLASS 52 DUCTILE IRON PIPE CONFORMING TO ANSI\AWWA C151\A21.51-91 FOR DUCTILE IRON PIPE

IRON PIPE. JOINTS SHALL BE EITHER PUSH-ON OR MECHANICAL JOINT AS REQUIRED.

3. ALL PIPE, FIXTURES AND FITTINFS MUST COMPLY WITH THE FEDERAL "SAFE DRINKING WATER ACT", SECTION 1417 WHICH REQUIRES ALL SURFACES IN CONTACT WITH POTABLE WATER CONTAIN NO MORE THAN 0.25% LEAD BY WEIGHT.

4. ALL WORK AND MATERIALS MUST MEET THE REQUIREMENTS OF THE TOWN OF NEWBURGH CONSOLIDATED WATER DISTRICT— STANDARD DESIGN AND CONSTRUCTION REQUIREMENTS FOR WATER DISTRIBUTION MAIN EXTENSION, OCT. 2001.

PIPE.

- A. DUCTILE IRON PIPE SHALL BE CLASS 52 WITH MECHANICAL-JOINT OR PUSH-ON JOINT CONNECTIONS. PIPE SHALL BE FURNISHED WITH A SEAL COATED CEMENT MORTAR LINING CONFORMING TO ANSI/AWWA C104/A21.4, LATEST VERSION. ALL BURIED PIPE SHALL BE FURNISHED WITH A STANDARD BITUMASTIC COATING CONFORMING TO A21.15, LATEST VERSION.
- B. PIPE SHALL BE MANUFACTURED IN ACCORDANCE WITH ANSI A21.50 AND AWWA C150/151, LATEST VERSION. C. FOR PUSH-ON JOINTS TWO(2) SUJCON BRONZE WEDGES SHALL BE
- C. FOR PUSH-ON JOINTS TWO(2) SILICON BRONZE WEDGES SHALL BE INSTALLED IN EACH JOINT AT THE 10 O'CLOCK AND 2 O'CLOCKPOSITIONS.

3. FITTINGS

A. ALL FITTINGS SHALL BE CLASS 52 CAST IRON OR DUCTILE IRON AND MECHANICAL JOINT CONFORMING TO ANSI/AWWA C100/A21.10, LATEST EDITION FOR DUCTILE AND GRAY IRON FITTINGS OR ASI/AWWA C153/A21.53, LATEST EDITION FOR DUCTILE IRON COMPACT

FITTINGS. B. FITTINGS SHALL HAVE A WORKING PRESSURE OF 250PSI FOR DUCTILE AND GRAY IRON FITTINGS AND 350PSI FOR DUCTILE IRON COMPACT

FITTINGS. C. FITTINGS SHALL BE FURNISHED WITH A SEAL COATED CEMENT MORTAR LINING WITH THE SAME THICKNESS SPECIFIED FOR THE

CORRESPONDING SIZE OF DUCTILE IRON PIPE.

4. JOINT RESTRAINT


A. THRUST RESTRAINT OF THE PIPE SHALL BE THROUGH THE USE OF JOINT RESTRAINT. THRUST BLOCK ARE NOT ACCEPTABLE. JOINT RESTRAINT SHALL BE THROUGH THE USE OF MECHANICAL JOINT PIPE WITH RETAINER GLANDS. ALL FITTINGS AND VALVES SHALL ALSO BE INSTALLED WITH RETAINER GLANDS FOR JOINT RESTRAINT. RETAINER GLAN SHALL BE EBAA IRON MEGALUG SERIES 1100 OR APPROVED EQUAL. THE USE OF A MANUFACTURED RESTRAINED JOINT PIPE IS ACCEPTABLE WITH PRIOR APPROVAL OF THE WATER DEPARTMENT.


5. VALVES & VALVE BOXS


A. ALL VALVES FOUR (4) INCHES THROUGH TWELVE (12) INCHES IN DIAMETER SHALL BE IRON BODY, BRONZE MOUNTED RESILIENT WEDGE GATE VALVES WITH MECHANICAL–JOINT ENDS. VALVES SHALL BE IN ACCORDANCE WITH THE LATEST VERSION OF AWWA C509.

- B. VALVES SHALL HAVE A MINIMUM OPERATING PRESSURE OF 250PSI AND FACTORY TESTED AT 500PSI.
- C. VALVES SHALL OPEN LEFT (COUNTER CLOCKWISE) WITH A STANDARD 2INCH SQUARE OPERATING NUT WITH ARROW CAST ONTO IT SHOWING THE DIRECTION OF OPENING. D. GATE VALVE SHALL MODEL A-2360-23 AS MANUFACTURED BY MUELLER CO
- OR EQUAL. E. VALVE BOXES SHALL BE INSTALLED WITH ALL VALVES.
- F. VALVE BOXES SHALL BE OF CAST-IRON, TELESCOPING, AT LEAST FIVE AND ONE-QUATER INCH (5/4") IN DIAMETER. VALVE BOXES SHALL BE TWO (2) PIECE AND OF THE LENGTH SO THAT WHEN THE TOP IS AT FINISHED GRADE, THE BOX WILL HAVE A EXTENSION RESERVE OF AT LEAST FIVE(5)
- INCHES. G. ALL VALVE BOXES SHALL BE FURNISHED TO MATCH THE SPECIFIC VALVE
- DIMENSIONS AND TRENCH DEPTH. H. VALVE BOXES SHALL BE PLUMB AND CENTERED OVER THE OPERATING NUT OF
- THE VALVE. I. ALL VALVE BOXES SHALL BE FURNISHED WITH A CAST IRON DROP STYLE COVER WITH THE WORD "WATER" AND A ARROW INDICATING THE DIRECTION OF VALVE OPENING.
- 7. ALL WATER SERVICE LINES TWO (2) INCHES IN DIAMETER AND SMALLER SHALL BE TYPE K COPPER TUBING. CORPORATION STOPS SHALL BE MUELLER H-15020 FOR 3/4 AND 1 INCH, MUELLER H-15000 OR B-25000 FOR 1 1/2 AND 2 INCH SIZES. CURB VALVES SHALL BE MUELLER H-1502-2 FOR 3/4 AND 1 INCH AND MUELLER B-25204 FOR 1 1/2 AND 2 INCH SIZES. CURB BOXES SHALL BE MUELLER H-10314 FOR 3/4 AND 1 INCH AND MUELLER H-10310 FOR 1 1/2 AND 2 INCH SIZES.
- 8. ALL PIPE INSTALLATION SHALL BE SUBJECT TO INSPECTION BY THE T.O.N. WATER DEPARTMENT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL INSPECTIONS AS REQUIRED WITH THE T.O.N. WATER DEPARTMENT.
- 9. THE WATER MAIN SHALL BE TESTED, DISINFECTED AND FLUSHED IN ACCORDANCE WITH THE T.O.N. REQUIREMENTS. ALL TESTING, DISINFECT ION AND FLUSHING SHALL BE COORDINATED WITH THE T.O.N. WATER DEPARTMENT. PRIOR TO PUTTING THE WATER MAIN IN SERVICE SATISFACTORY SANITARY RESULTS FROM A CERTIFIED LAB MUST BE SUBMITTED TO THE T.O.N. WATER DEPARTMENT. THE TEST SAMPLES MUST BE COLLECTED BY A REPRESENTATIVE OF THE TESTING LABORATORY AND WITNESSED BY THE WATER DEPARTMENT.
- 10. CONTRACTOR SHALL DIG TEST HOLE PRIOR TO MAIN EXTENSION TO VERIFY EXISTING MAIN, VALVE AND FITTINGS. TOWN ENGINEER AND WATER DEPARTMENT SHALL BE NOTIFIED OF TEST HOLE SCHEDULE.
- 11. THE TOWN OF NEWBURGH WATER SYSTEM SERVING THIS AREA OF DEVELOPMENT, REQUIRED THAT EACH HOMEOWNER MAINTAIN AN INDIVIDUAL WATER BOOSTER SYSTEM. EACH INDIVIDUAL PUMP AND HYDROPENUMATIC SYSTEM SHALL PROVIDE WATER PRESSURES BETWEEN 30 AND 50psi WITHIN THE HOME.
- 12. THE DOUBLE CHECK VALVE BACKFLOW PREVENTOR MUST BE MAINTAINED BY THE HOMEOWNER AND INSPECTED ANNUALLY BY A NYS CERTIFIED TESTER, AND A COPY OF THE REPORT MUST BE SUBMITTED TO THE TOWN OF NEWBURGH WATER DEPARTMENT.
- 13. DUE TO EXISTING LIMITATIONS IN THE TOWN OF NEWBURGH WATER SUPPLY SYSTEM, FIRE FLOW IN THIS PROJECT WILL BE BELOW THE NEEDED FIRE FLOWS AS ESTABLISHED BY THE INSURANCE SERVICES OFFICE IN THEIR "FIRE SUPPRESSION RATING SCHEDULE"


	THIS SHEET IS INVALID AND VOID UNLESS ACCOMPANIED BY REMAINING SHEETS IN SET.						
	ENGINEER	TALCO	OTT ENGL	NEERING	DESI	GN PLL	C
	Shite OF NEW OF		(1	GARDNERTOWN RO, EWBURGH, NY 1253 (845)—569—8400 FAX)(845)—569—458 OTTDESIGN12@GMAI	50 83		
	1-CC		CHAI	SUBDIVISION DWICK WO 300, SBL 14-	ODS	Ď	
	ROFESSIONAL	TOW		URGH, ORANG		TY, NY	
D PB COMMENTS		DATE	SCALE	JOB NUMBER		SHEET NUMBER	
D PB COMMENTS	CHARLES T. BROWN,P.E.	01/11/18	N.T.S.	17100- M	MR	6 OF 7	







REVISIONSREV.:DATE:BY:DESCRIPTION:205/21/21RBMREVISEDPERBOARDPBCOMMENTS106/08/20RBMREVISEDPERBOARDPBCOMMENTS



THRUST BLOCK DETAIL

(NOT TO SCALE)

