

MICHAEL J. LAMOREAUX, P.E. (NY, NJ, PA, VT, VA & CT) MICHAEL W. WEEKS, P.E. (NY, NJ & PA) LYLE R. SHUTE, P.E., LEED-AP (NY, NJ, PA) PATRICK J. HINES Main Office 33 Airport Center Drive Suite 202 New Windsor, New York 12553

(845) 567-3100 fax: (845) 567-3232

e-mail: mheny@mhepc.com

Principal Emeritus:

RICHARD D. McGOEY, P.E. (NY & PA)

TOWN OF NEWBURGH
PLANNING BOARD
TECHNICAL REVIEW COMMENTS

PROJECT: HANOVER ROUTE 32 SUBDIVISION

PROJECT NO.: 21-06

PROJECT LOCATION: SECTION 2, BLOCK 1, LOT 57.2

REVIEW DATE: 11 JUNE 2021 MEETING DATE: 17 JUNE 2021

PROJECT REPRESENTATIVE: ENGINEERING AND SURVEYING PROPERTIES

- **1.** Orange County Planning 239 review has been received identifying no comments and local determination.
- **2.** Any approval resolution should contain a requirement that each of the individual lots receive driveway approval from the NYSDOT.
- **3.** The project requires coverage on the NYSDEC SPDES Stormwater Permit. A municipal authorization will be issued upon request.
- **4.** Recreation fees in accordance with the Town's fee schedule of \$2,000.00 per lot are required.

Respectfully submitted,

McGoey, Hauser and Edsall Consulting Engineers, D.P.C.

Patrick J. Hines

Principal

PJH/dns



Montgomery Office:

71 Clinton Street Montgomery, NY 12549 phone: (845) 457-7727 fax: (845) 457-1899 Warwick Office: 17 River Street Warwick, NY 10990 phone: (845) 986-7737 fax: (845) 986-0245

www.EngineeringPropertiesPC.com

May 7, 2021

Town of Newburgh Planning Board 21 Hudson Valley Professional Plaza Newburgh, NY 12550

ATTN: John Ewasutyn, Chairman

RE: W.O. # 1051.11

PB APPLICATION 2021-06
HANOVER RTE 32 SUBDIVISION

TAX LOT # 2-1-57.2 COMMENT RESPONSE

Dear Mr. Ewasutyn:

We are in receipt of the comment memo regarding the above-mentioned project dated April 9, 2021 from MH&E Consulting Engineers, D.P.C. Below is a comment-by-comment response;

- 1. As part of this re-submission please find the approval letter from the NYS Department of Transportation attached.
- 2. Limits of disturbance have been included on Sheet C-101. A draft Notice of Intent has been prepared and is attached. The Notice of Intent will be finalized upon Planning Board approval and submitted to receive coverage under the NYSDEC Stormwater SPDES Permit prior to start of construction.
- 3. A common driveway access and maintenance agreement for Lots 4 & 5 will be provided prior to final approval.
- 4. It is our understanding that the plan set was forwarded to Orange County Planning for review on April 19th.
- 5. The septic system location on proposed Lot 3 has been relocated so that it is more than 100 hundred feet away from the existing wetlands.
- 6. The septic system location on proposed Lot 3 has been relocated. Please refer to Sheet C-300 for the corresponding percolation and deep test pit results.
- 7. A copy of the Wetland Delineation report will be provided to the Town once it is complete.
- 8. No response required.

If you have any additional questions and/or comments please don't hesitate to contact this office.

Sincerely,

Engineering & Surveying Properties, PC

Ross Winglovitz, P.E.

Principal

Reuben Buck Project Engineer



ANDREW M. CUOMO Governor

MARIE THERESE DOMINGUEZ
Commissioner

LANCE MacMILLAN, P.E. Regional Director

April 20, 2021

Ross Winglovitz, P.E. Engineering Properties 71 Clinton Street Montgomery, NY 12549

RE:

HANOVER ROUTE 32 SUBDIVISION
NYS ROUTE 32, TAX MAP SBL: 2-1-57.2
TOWN OF NEWBURGH, ORANGE COUNTY

Dear Mr. Winglovitz,

The Department is in receipt of your plan, dated 4/5/2021, for the referenced project. We are acceptable to this subdivision plan with four driveways proposed to serve five residential properties. The common shared driveway serving Lots #4 and #5 shall be constructed based upon regular single-family residential driveway standards.

As per our field visit, the four locations shown on the plan are also acceptable. Since this portion of NYS Route 32 has a posted Speed Limit of 55 mph, the owners of each residential driveway shall make every effort to keep the NYS ROW clear of sight obstructions to meet the required sight distances. The obstructions shall be eliminated during the construction stages of each driveway and maintained throughout occupancy of the properties.

Each individual property owner of Lots #1, #2 and #3, and the combined owners of Lot #4 and #5 shall be responsible for obtaining a Highway Work Permit for access from the state highway. They shall obtain permits from the Department prior to beginning construction within their lots. Each access shall conform to current NYSDOT standards and specifications. They shall contact the Permit Field Engineer to begin the process of obtaining the HWP.

living - Corbone

Respectfully,

Siby Mary Zachariah-Carbone Permit Field Engineer, Res. 8-4

Eastern Orange County

NOTICE OF INTENT



New York State Department of Environmental Conservation Division of Water

625 Broadway, 4th Floor

NYR						
	(fo	r D	EC.	1186	on l	v)

Albany, New York 12233-3505

Stormwater Discharges Associated with Construction Activity Under State Pollutant Discharge Elimination System (SPDES) General Permit # GP-0-20-001 All sections must be completed unless otherwise noted. Failure to complete all items may result in this form being returned to you, thereby delaying your coverage under this General Permit. Applicants must read and understand the conditions of the permit and prepare a Stormwater Pollution Prevention Plan prior to submitting this NOI. Applicants are responsible for identifying and obtaining other DEC permits that may be required.

-IMPORTANT-RETURN THIS FORM TO THE ADDRESS ABOVE

OWNER/OPERATOR MUST SIGN FORM

	Owner/Operator Information ner/Operator (Company Name/Private Owner Name/Municipality Name)																																							
Ow	ne:	r/()pe	ra	to	r (Coi	mpa	ny	, N	am	e/I	ri	va	te	Ow	ne	r l	Na	me,	/Mu	ni	cir	oa	lit	У	Na	me	:)	1 -	. 1	-	: :					- 54 - 52 <u>- 5</u>		
Η	a	n	0	v	е	r		D	е	v	е	1	0	р	m	ω	n	t	,		L	L	C																	
Ow	ne:	r/0	pe	ra	to	r C	on	tac	:t	Pe	rs	on	La	st	Na	ame	(NO'	Г	COI	usu	LT	ANI	[]	Ţ.															
			Ī																		T		Π	Ť	T	Τ								Γ			T			T
Ow	ne.	r/C) pe	ra	to	r C	on	tac	t	Рe	rs	on	Fi	rs	t 1	Van	ıe				. 1									-							-	:-		
Оw	ne:	r/C)pe	ra	to	r M	lai.	lin	g	Ad	dr	288	3																	, · ;							÷.			
7.	1		C	1	i	n	t	0	n		S	t	r	е	е	t																					T			
	ity																																							
M	0	n	t	g	0	m	е	r	У											L					<u> </u>													L		
_	ate Y	1. 1				Z:	lp _ 2	5	4	9]-		L	I																										
Ph	one	e (Ow	ne	r/(Эре	ra	tor)						Fa	x	(O _V	vne	<u>r,</u>	/Op	era	ato	<u>r)</u>				<u> </u>													
8	4	5	-	4	5	7	1	7	7	2	7				8	4	5	-	4	! 5	7	-	1	. 8	3	9	9													
Εm	ai.	L (Ow	ne	r/(Эре	rai	tor)									.									<u> </u>													
																					Π				T										Ė					
	I 		_		I T	<u>!</u>	LI		!	7.	"	-								 	<u> </u>	l I	<u> </u>	<u> </u>	<u>↓</u> Т	+	1	+				_			_		_	$^{\perp}$	<u> </u>	<u> </u>
	<u> </u>				<u> </u>																															L	<u></u>			
FE	D TAX ID (not required for individuals)																																							

	t Sit	te Ini	forma	atio	n				1.								
Project/Site Name	***								-								
Hanover Route	3 2	Su	b d	i v	li	s i	0	n									
Street Address (NOT P.O. BOX)																	
NYSRoute32																	
Side of Street																	
○ North ○ South ○ East ● West	Ē																
City/Town/Village (THAT ISSUES E	UILDING	PER	MIT)	. 1					91		 		· · · · ·				<u> </u>
Town of Newbur	gh		Щ									1				<u> </u>	
State Zip N Y 1 2 5 8 9 -	County	/ a n	g e					-			DI	EC	Reg	ioi	n		
Name of Nearest Cross Street			<u> </u>			<u> </u>					 7.5				٠.		
East Road			Щ.				<u> </u>										1
Distance to Nearest Cross Street	(Feet)					ojed Nort				lat u th							
Tax Map Numbers Section-Block-Parcel					Ta	x M	ap	Nun	nbe	rs	-						
2 - 1 - 5 7 .	2						1										

1. Provide the Geographic Coordinates for the project site in NYTM Units. To do this you <u>must</u> go to the NYSDEC Stormwater Interactive Map on the DEC website at:

www.dec.ny.gov/imsmaps/stormwater/viewer.htm

Zoom into your Project Location such that you can accurately click on the centroid of your site. Once you have located your project site, go to the tool boxes on the top and choose "i"(identify). Then click on the center of your site and a new window containing the X, Y coordinates in UTM will pop up. Transcribe these coordinates into the boxes below. For problems with the interactive map use the help function.

x	Coc	rdi	nate	es (Eas	ting	Į)
	6	0	8	4	1	6	

Y C	cor	dina	ates	(N	orth	ning	1
1	0	0	5	1	6	8	

- 2. What is the nature of this construction project?
 - New Construction
 - O Redevelopment with increase in impervious area
 - O Redevelopment with no increase in impervious area

activities.

3. Select the predominant land use for both part of the SELECT ONLY ONE CHOICE FOR EACH	ore and post development conditions.
Pre-Development Existing Land Use	Post-Development Future Land Use
● FOREST	O SINGLE FAMILY HOME Number of Lots
O PASTURE/OPEN LAND	● SINGLE FAMILY SUBDIVISION 0 0 5
O CULTIVATED LAND	O TOWN HOME RESIDENTIAL
O SINGLE FAMILY HOME	O MULTIFAMILY RESIDENTIAL
O SINGLE FAMILY SUBDIVISION	O INSTITUTIONAL/SCHOOL
O TOWN HOME RESIDENTIAL	O INDUSTRIAL
O MULTIFAMILY RESIDENTIAL	○ COMMERCIAL
O INSTITUTIONAL/SCHOOL	O MUNICIPAL
O INDUSTRIAL	○ ROAD/HIGHWAY
O COMMERCIAL	O RECREATIONAL/SPORTS FIELD
O ROAD/HIGHWAY	OBIKE PATH/TRAIL
O RECREATIONAL/SPORTS FIELD	OLINEAR UTILITY (water, sewer, gas, etc.)
OBIKE PATH/TRAIL	O PARKING LOT
O LINEAR UTILITY	O CLEARING/GRADING ONLY
O PARKING LOT	O DEMOLITION, NO REDEVELOPMENT
OOTHER	O WELL DRILLING ACTIVITY * (Oil, Gas, etc.)
	O OTHER
*Note: for gas well drilling, non-high volume	hydraulic fractured wells only
4. In accordance with the larger common plan of enter the total project site area; the total existing impervious area to be disturbed (activities); and the future impervious area disturbed area. (Round to the nearest tent)	al area to be disturbed; for redevelopment a constructed within the h of an acre.) Future Impervious
	ting Impervious Area Within To Be Disturbed Disturbed Area
53.7 3.5	
5. Do you plan to disturb more than 5 acres o	f soil at any one time? O Yes • No
6. Indicate the percentage of each Hydrologic A B	Soil Group(HSG) at the site. C D
5 % 0 %	3 9 % 5 6 %
7. Is this a phased project?	○ Yes • No
8. Enter the planned start and end dates of the disturbance Start Da 0 7 /	End Date 0 1 / 2 0 2 1 - 0 9 / 3 0 / 2 0 2 2

<u> </u>			len sch				ne	ne	ea:	re	st		sui	rf	ace	e v	vat	er	bc	ody	у (i.e	es)	t	:0	wh	nic	h	CC	on	st:	ru	cti	or.	ıs	it	<u> </u>	ru	noi	ff	wi	11		
Νa	me				-																																							
0	n	5	i	t	Te	∍	1	w	е	t	: :	L	a	n	d	s		T																										
片		 	<u> </u>	<u> </u>	<u> </u> 	$\frac{\perp}{1}$	$\frac{1}{1}$	<u> </u>		<u> </u>	$\frac{\perp}{\Gamma}$	<u> </u>			+	<u> </u>	T	T	<u> </u>	\exists	_	L [+	T	\exists	7		<u> </u>	+	T	+	 T			_			<u> </u>		<u></u>	<u> </u>	<u> </u>		
L_	Ļ_	L		1_	<u> </u>					L		_		-	<u> </u>			<u> </u>		_	,	L			_	_		<u> </u>	<u> </u>			_	-	7.		<u> </u>				1	<u> </u>		<u> </u>	ب
S	a. O	We	Ty etl																				on swe			b)																		
		We	et1	an	d	/	St	at	е	J۱	ur.	is	di	ct	io	n	Of	£	Si	te). }																							
		We	etl	an	d	/	Fe	de	ra	1	Jı	ır	is	di	.ct	io	n (On	S	it	e.	(Ans	SW.	er	9	b)		21"															
	0	We	etl	an	d.	/	Fe	de	ra	ıl	Jı	ır	is	di	ct	io	n () Df	f	Si	.te	•																						
	Ö	St	tre	am	/	C	re	ek	C	n	S.	Lt	e																															
	0	St	tre	am	1	C.	re	ek	C	f:	f:	Si	: te																															
	0	R:	ive	r	On	S	it	e																																				
			ive	. •				1.1								٠,		 :						9	b.		Η	01	V	va:	s t	h	€ W	et	la	nd	i	der	nti	Lfi	ed	?		
			ake	٠.									1.														` .	· .	gu.	1 _	L ~ .		1.6											
	Ţ		ake																															Ţ.,	'on	611	ılt	3 n	+					
			the						Si	+ 4																							_		٠.				7.1	٦f	Er	ori:	200	ers
			the			7																							nei				2			.y	CO	тÞ	, ,	O.L.		ıy	100	.1.0
	O				I y	pe	Ĭ	1, 1,									L											, С.	.161															
	0.		30 Is	3(t	d) hi	.s	eg pr	me 	ent	: -ct	in 1	00	.pr	e	ndi d i	.x .n	E	of	- G	P-	-0-	-2	ti 0- Wa	00	1?											a			Y			O N		
·			Ar	pe	no	lix	. C	; c)	-G	P-	0-	-20)—	001	L?				• .					· .								•									● N		-
1	2.		ar Wa		s rs	as ?	so	ci	.at	:e	d	wi	th	1 2	AΑ								ato si:															C	Y	es	•	● N	0	
1	3.		ex ic	is len	ti ti	ng fi	i ed	mp la	ei is	cv a	io n	us E	or	0	ver F c	r a	nd th	e e	he US	re D <i>P</i>	e t	ch So	b ie i il	So S	il ur	s ve	10	pe			ase	• i	is						Y	es		● N	0	
		:	-							•											• <u>L</u>				2		•											-					-	
1	4.		re		la																		a s				jа	C€	ent									C) Y	es	(● N	0	

15.	Does the site runoff enter a separate storm sewer system (including roadside drains, swales, ditches, culverts, etc)?	
16.	What is the name of the municipality/entity that owns the separate storm sewer system?	
17.	Does any runoff from the site enter a sewer classified OYes No OUnknown as a Combined Sewer?	
18.	Will future use of this site be an agricultural property as defined by the NYS Agriculture and Markets Law? ○ Yes ● No	
19.	Is this property owned by a state authority, state agency, federal government or local government?	
20.	Is this a remediation project being done under a Department approved work plan? (i.e. CERCLA, RCRA, Voluntary Cleanup O Yes ● No Agreement, etc.)	
21.	Has the required Erosion and Sediment Control component of the SWPPP been developed in conformance with the current NYS Yes O No Standards and Specifications for Erosion and Sediment Control (aka Blue Book)?	
22.	Does this construction activity require the development of a SWPPP that includes the post-construction stormwater management practice component (i.e. Runoff Reduction, Water Quality and Quantity Control practices/techniques)? If No, skip questions 23 and 27-39.	
23.	Has the post-construction stormwater management practice component of the SWPPP been developed in conformance with the current NYS O Yes O No Stormwater Management Design Manual?	

24.	Tì	ıe	Sto	orm	ıwa	te	r I	Pol	lu	tic	on	Pr	ev	ent	ic	n	Pl	an	(S	WP	PP) v	ıas	р	rep	oar	ed	b	у:		; ; ;						
• 1	Proi	es	si	one	al	En	gi	nee	er	(P	.E	.)											i S														
0	Soi:	L a	nd	Wa	ate	r	Co	nse	erv	at.	1.01	n I)is	tr	ic	t ((SW	CD)						<i>.</i>												
01	Reg:	st	er	ed	La	nd	sc	ape	A	rcl	hi	tec	st	(R	.L	. A)																					
0	Cer	if	ie	d I	Pro	fe	ss.	ior	al	iı	n I	Erc	si	on	aı	nd	Se	di	meı	nt	Co	nt	rol	(CP	ES	2)										
0 (Owne	er/	Op	era	ito	r			.1																										j.		
0	Othe	er			1	_	1	_		T-	· ·			· -	Т	-		_			· · · · ·		_	· ·	+	· .	<u> </u>	.			·		-				
			1	1				1	1						1					\perp				1				\perp	1			1.			_]	 	
																									7 J.S.												
SWPPP	Pre	par	er																	1				· · .	· 	F -				T .	-	· :	1	<u> </u>			· ·
E n g	y i	n	е	е	r	i	n	g		&		S	u	r	v	е	У	i	n	g		P	r	0	р	е	r	t	ļ i	е	ន	<u> </u>	P	•	C	•	
Contac	t N	ame) (La	st	, .	Spa	ce	<u>, </u>	Fir	st)						·								:			,·	,					:		·
Win	ı g	1	0	v	i	t	Z	,		R	0	s	s																			<u></u>					
Mailin	g A	ddr	es	s									-,-	٠					,			-		52 <u>.</u> -				ı <u>.</u>							· .	1	
7 1	C	1	i	n	t	0	n		S	t	r	е	е	t		L					l																
City						-							<u>:</u>			·		1								· .			·.			· .			1		
M o n	ı t	g	0	m	е	r	У											L.,														ļ	<u>l</u>	<u> </u>			
State	Zi									· ·																					200	1 4					
NY	1	2	5	4	9	_																															
Phone	.			_1	1										:			٠,٠	Fax								-	· .	· ·		: ••						
8 4 5	<u> </u>	4	5	7	-	7	7	2	7	., a -									8	4	5	-	4	5	7	-	1	8	9	9							
Email	. T				^j							-					· ·	<u>. </u>	Т	Γ-					· ·	•		1	Ι	1	1	1	1	, 			
ros	3 S	@	е	р	_	р	С	·	С	0	m								<u> </u>			<u> </u>	<u> </u>		<u> </u>			<u> </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>		_
																			L.,									_			L					<u> </u>	<u></u>
	1			٠.					1 .	,									-								_	- 1						. 1	1.34)

SWPPP Preparer Certification

I hereby certify that the Stormwater Pollution Prevention Plan (SWPPP) for this project has been prepared in accordance with the terms and conditions of the GP-0-20-001. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of this permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

First Name	MI
Ross	A
Last Name	
Winglovitz	
Signature (
	Date 0 4 / 2 1 / 2 0 2 1
Page 6 of 14	

25.	Has a construction sequence practices been prepared?	scl	ned	ule	for	î t	he	pla	nne	d m	an	agei	men	t			Y	(es		O 1	10	
26.	Select all of the erosion as employed on the project site		sed	imer	nt d	con	ntro	ol p	rac	tic	es	tha	at	wi]	11	be						
	Temporary Structura	1							Veç	jet.	at	iv€	<u>M</u>	lea	su	re	5					
	O Check Dams							() E	rus	h M	at	tin	g									
	\bigcirc Construction Road Stabil	iza	tic	on				\circ	une	st	ab	ili	zat	io	n							
	O Dust Control							O G	ras	sed	W	ate	rwa	У								
	○ Earth Dike							O M	ulc	hin	g											
	O Level Spreader							O F	rot	ect	in	g V	ege	ta	tic	n						
	O Perimeter Dike/Swale							O R	ecr	eat	io	n A	rea	. I	mpr	ove	eme	ent	:			
	O Pipe Slope Drain							O s	eed	ling												
	O Portable Sediment Tank							O s	odd	ling												
	O Rock Dam							O 8	tra	w/H	ay	Ba	le	Di	ke							
	O Sediment Basin							O 8	tre	amb	an	k P	rot	ec	tic	n						
	O Sediment Traps							\circ	emp	ora	ry	Sw	ale)								
	Silt Fence							OI	ops	oil	in	g										
	Stabilized Construction	Ent	rar	ce				$\circ v$	ege	tat	in	g W	ate	rw	ays	,						
	O Storm Drain Inlet Protec	tio	n						Per	ma	ne	nt	st		ct	11 r 2	a 1					
	O Straw/Hay Bale Dike																	-				
	O Temporary Access Waterwa	уС	ros	ssin	g			\bigcirc D	ebr	is	Ва	sin	•									
	O Temporary Stormdrain Div	ers	ior	ı				\bigcirc D	ive	rsi	on	•										
	Temporary Swale							\bigcirc G	rac	le S	ta	bil	iza	ti	on	Str	cuc	ctu	re			
	O Turbidity Curtain							• I	and	l Gr	ad	ing										
	○ Water bars							OI	ine	ed W	at	erw	ay	(R	ock	:)						
									ave	ed C	ha	nne	1 (Co	ncr	ete	∌)					
	Biotechnical							O F	ave	ed F	'lu	me										
	OBrush Matting							O F	eta	ini	ng	Wa	11									
	○ Wattling							\circ	ipr	ap	sı	ope	Pr	ot	ect	ior	1					
	-							\bigcirc P	ock	Ou	tl	et	Pro	te	cti	.on						
<u>Otl</u>	<u>her</u>							O s	tre	amb	an	k P	rot	ec	tic	n						
											$ \top $											
			\exists								T		T									İ

Post-construction Stormwater Management Practice (SMP) Requirements

Important: Completion of Questions 27-39 is not required

if response to Question 22 is No.

- 27. Identify all site planning practices that were used to prepare the final site plan/layout for the project.
 - O Preservation of Undisturbed Areas
 - O Preservation of Buffers
 - O Reduction of Clearing and Grading
 - O Locating Development in Less Sensitive Areas
 - O Roadway Reduction
 - O Sidewalk Reduction
 - O Driveway Reduction
 - O Cul-de-sac Reduction
 - O Building Footprint Reduction
 - O Parking Reduction
- 27a. Indicate which of the following soil restoration criteria was used to address the requirements in Section 5.1.6("Soil Restoration") of the Design Manual (2010 version).
 - O All disturbed areas will be restored in accordance with the Soil Restoration requirements in Table 5.3 of the Design Manual (see page 5-22).
 - O Compacted areas were considered as impervious cover when calculating the **WQv Required**, and the compacted areas were assigned a post-construction Hydrologic Soil Group (HSG) designation that is one level less permeable than existing conditions for the hydrology analysis.
- 28. Provide the total Water Quality Volume (WQv) required for this project (based on final site plan/layout).

Total WQv Required acre-feet

29. Identify the RR techniques (Area Reduction), RR techniques (Volume Reduction) and Standard SMPs with RRv Capacity in Table 1 (See Page 9) that were used to reduce the Total WQv Required (#28).

Also, provide in Table 1 the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

Note: Redevelopment projects shall use Tables 1 and 2 to identify the SMPs used to treat and/or reduce the WQv required. If runoff reduction techniques will not be used to reduce the required WQv, skip to question 33a after identifying the SMPs.

7738089822

Table 1 - Runoff Reduction (RR) Techniques and Standard Stormwater Management Practices (SMPs)

	Total Contributing	Total Contribut	ting
RR Techniques (Area Reduction)	Area (acres)	Impervious Area(a	acres
O Conservation of Natural Areas (RR-1)		and/or .	
O Sheetflow to Riparian Buffers/Filters Strips (RR-2)		and/or .	
○ Tree Planting/Tree Pit (RR-3)		and/or .	
O Disconnection of Rooftop Runoff (RR-4)		and/or .	
RR Techniques (Volume Reduction)			\Box
○ Vegetated Swale (RR-5) ······			
O Rain Garden (RR-6)			
○ Stormwater Planter (RR-7)			
○ Rain Barrel/Cistern (RR-8)			
O Porous Pavement (RR-9)			
○ Green Roof (RR-10)			
Standard SMPs with RRv Capacity			
O Infiltration Trench (I-1) ······			
O Infiltration Basin (I-2) ·····			Ш
O Dry Well (I-3)			Ш
O Underground Infiltration System (I-4)			
O Bioretention (F-5)			
○ Dry Swale (0-1) · · · · · · · · · · · · · · · · · · ·	• • • • • • • • • • • • • • • • • • • •		
Standard SMPs			
O Micropool Extended Detention (P-1)			\square
○ Wet Pond (P-2) ····································		• • • • • • • • • • • • • • • • • • • •	
\bigcirc Wet Extended Detention (P-3) $\cdots\cdots$			
○ Multiple Pond System (P-4) ······	• • • • • • • • • • • • • • • • • • • •		Ш
O Pocket Pond (P-5) ·····	• • • • • • • • • • • • • • • • • • • •		
○ Surface Sand Filter (F-1) · · · · · · · · · · · · · · · · · · ·	• • • • • • • • • • • • • • • • • • • •		
O Underground Sand Filter (F-2) ······	• • • • • • • • • • • • • • • • • • • •		
O Perimeter Sand Filter (F-3) ······			
O Organic Filter (F-4)			
\bigcirc Shallow Wetland (W-1)			Ш
O Extended Detention Wetland (W-2)			
O Pond/Wetland System (W-3)			
O Pocket Wetland (W-4)			
○ Wet Swale (0-2)			

Table 2 -Alternative SMPs (DO NOT INCLUDE PRACTICES BEING USED FOR PRETREATMENT ONLY) Total Contributing Alternative SMP Impervious Area (acres) O Hydrodynamic O Wet Vault O Media Filter Other Provide the name and manufacturer of the Alternative SMPs (i.e. proprietary practice(s)) being used for WQv treatment. Name Manufacturer Note: Redevelopment projects which do not use RR techniques, shall use questions 28, 29, 33 and 33a to provide SMPs used, total WQv required and total WQv provided for the project. Indicate the Total RRv provided by the RR techniques (Area/Volume Reduction) and 30. Standard SMPs with RRv capacity identified in question 29. Total RRv provided acre-feet 31. Is the Total RRv provided (#30) greater than or equal to the total WQv required (#28). O Yes O No If Yes, go to question 36. If No, go to question 32. 32. Provide the Minimum RRv required based on HSG. [Minimum RRv Required = (P)(0.95)(Ai)/12, Ai=(S)(Aic)] Minimum RRv Required acre-feet 32a. Is the Total RRv provided (#30) greater than or equal to the Minimum RRv Required (#32)? O Yes \bigcirc No If Yes, go to question 33. Note: Use the space provided in question #39 to summarize the specific site limitations and justification for not reducing 100% of WQv required (#28). A detailed evaluation of the specific site limitations and justification for not reducing 100% of the WQv required (#28) must also be included in the SWPPP. If No, sizing criteria has not been met, so NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.

33.	Identify the Standard SMPs in Table 1 and, if applicable, the Alternative SMPs in
JJ.	Table 2 that were used to treat the remaining total WQv (=Total WQv Required in 28 - Total RRv Provided in 30).
	Also, provide in Table 1 and 2 the total $\underline{\text{impervious}}$ area that contributes runoff to each practice selected.
	<u>Note</u> : Use Tables 1 and 2 to identify the SMPs used on Redevelopment projects.
33a.	Indicate the Total WQv provided (i.e. WQv treated) by the SMPs identified in question #33 and Standard SMPs with RRv Capacity identified in question 29. WQv Provided
<u>Note</u> :	For the standard SMPs with RRv capacity, the WQv provided by each practice = the WQv calculated using the contributing drainage area to the practice - RRv provided by the practice. (See Table 3.5 in Design Manual)
34.	Provide the sum of the Total RRv provided (#30) and the WQv provided (#33a).
35:	Is the sum of the RRv provided (#30) and the WQv provided (#33a) greater than or equal to the total WQv required (#28)? O Yes O No If Yes, go to question 36. If No, sizing criteria has not been met, so NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.
36.	Provide the total Channel Protection Storage Volume (CPv) required and provided or select waiver (36a), if applicable.
	CPv Required CPv Provided
	acre-feet acre-feet
36a. 5	The need to provide channel protection has been waived because: O Site discharges directly to tidal waters or a fifth order or larger stream. O Reduction of the total CPv is achieved on site through runoff reduction techniques or infiltration systems.
37.	Provide the Overbank Flood (Qp) and Extreme Flood (Qf) control criteria or select waiver (37a), if applicable.
	Total Overbank Flood Control Criteria (Qp)
	Pre-Development Post-development
	CES CES

Total Extreme Flood Control Criteria (Qf)

Post-development

CFS

Pre-Development

CFS

	<pre>O Site discharges directly to tidal waters or a fifth order or larger stream. O Downstream analysis reveals that the Qp and Qf controls are not required</pre>
38.	Has a long term Operation and Maintenance Plan for the post-construction stormwater management practice(s) been O Yes O No developed?
	If Yes, Identify the entity responsible for the long term Operation and Maintenance
39.	Use this space to summarize the specific site limitations and justification for not reducing 100% of WQv required(#28). (See question 32a) This space can also be used for other pertinent project information.
-	

37a. The need to meet the Qp and Qf criteria has been waived because:

4285089826


40.	Identify other DEC permits, existing and new, that are required for this project/facility.								
	O Air Pollution Control								
	O Coastal Erosion								
	O Hazardous Waste								
	O Long Island Wells								
	O Mined Land Reclamation								
	O Solid Waste								
	O Navigable Waters Protection / Article 15								
	O Water Quality Certificate								
	O Dam Safety								
	O Water Supply								
	O Freshwater Wetlands/Article 24								
	O Tidal Wetlands								
	O Wild, Scenic and Recreational Rivers								
	O Stream Bed or Bank Protection / Article 15								
	O Endangered or Threatened Species (Incidental Take Permit)								
	O Individual SPDES								
	O SPDES Multi-Sector GP N Y R								
	O Other								
	● None								
41.	Does this project require a US Army Corps of Engineers O Yes No								
	Wetland Permit? If Yes, Indicate Size of Impact.								
42.	Is this project subject to the requirements of a regulated, traditional land use control MS4? • Yes O No (If No, skip question 43)								
43.	Has the "MS4 SWPPP Acceptance" form been signed by the principal executive officer or ranking elected official and submitted along with this NOI?								
44.	If this NOI is being submitted for the purpose of continuing or transferring coverage under a general permit for stormwater runoff from construction activities, please indicate the former SPDES number assigned.								

Owner/Operator Certification

I have read or been advised of the permit conditions and believe that I understand them. I also understand that, under the terms of the permit, there may be reporting requirements. I hereby certify that this document and the corresponding documents were prepared under my direction or supervision. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that coverage under the general permit will be identified in the acknowledgment that I will receive as a result of submitting this NOI and can be as long as sixty (60) business days as provided for in the general permit. I also understand that, by submitting this NOI, I am acknowledging that the SWPPP has been developed and will be implemented as the first element of construction, and agreeing to comply with all the terms and conditions of the general permit for which this NOI is being submitted.

Print First Name		MI	
Ross		A	
Print Last Name		<u>4.3.14</u> 114. 14. 14.	
Winglovit	z		
Owner/Operator Signa	ture,		
	11/7	Date	
		0 4 / 2	2 1 / 2 0 2 1





SEPTIC SYSTEM DESIGN SCHEDULE

				5.54				
LOT	NUMBER OF BEDROOMS	DESIGN PERC RATE (min)	FLOW RATE (GPD)	APPLICATION RATE (GPD/Sq. ft.)	REQUIRED AREA (Sq. ft.)	REQUIRED ABSORPTION FIELD LENGTH (ft)	REQUIRED FIELD LENGTH (ft) BASED USING GRAVELESS CHAMBERS (25% REDUCTION)	PROPOSED ABSORPTION FIELD LENGTH (ft)
1	4	10	440	0.90	488.9	245.3	184	5 LATERALS @ 40' 5 ROWS OF 6 CHAMBERS
2	4	14	440	0.80	550.0	276.0	207	4 LATERALS @ 55' 4 ROWS OF 11 CHAMBERS
3	4	34	440	0.50	880.0	440.0	330	12 LATERALS @ 30' 12 ROWS OF 6 CHAMBERS
4	4	31	440	0.50	880.0	440.0	330	6 LATERALS @ 55' 6 ROWS OF 11 CHAMBERS
5	4	22	440	0.60	733.3	366.7	275	8 LATERALS @ 35' 8 ROWS OF 7 CHAMBERS


PERCOLATION TEST RESULTS


STABLIZEI RATE	7 · · · · · · · · · · · · · · · · · · ·	STS		TOPWATCH USI IME FOR 1" DRO		TIME	PERC HOLE DIA	PERC HOLE DEPTH	PERC HOLE#	LOT#
				-		FINISH				
8 MIN	†	RVALS	OR TIMED INTER	WATCH USED F	STOP	START	10"	24"	01/22/21 PT-03	1
	**************************************		00:07:40	00:07:23	00:04:10	TIME				
10 MIN	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,					FINISH				
		D INTERVALS	USED FOR TIME	STOPWATCH		START	10"	24"	03/05/21 PT-03	1 1
			00:09:18	00:08:41	00:08:24	TIME			1 1 00	
						FINISH				
11 MIN		D INTERVALS	USED FOR TIME	STOPWATCH		START	10"	24"	01/22/21 PT-02	2
			00:10:03	00:09:28	00:04:27	TIME			02	
						FINISH				
14 MIN		D INTERVALS	JSED FOR TIME	STOPWATCH		START	10"	24"	03/05/21 PT-04	2
		00:13:10	00:13:06	00:11:34	00:08:24	TIME				
34 MIN						FINISH				
		D INTERVALS	JSED FOR TIME	STOPWATCH		START	10"	24"	01/22/21 PT-04	3
	Í		00:33:05	00:13:15	00:19:05	TIME				
					***************************************	FINISH	***************************************			
5 MIN		D INTERVALS	JSED FOR TIME	STOPWATCH		START	10"	24"	04/28/21 PT-01	3
			00:04:39	00:04:28	00:02:51	TIME				1.1
	***************************************					FINISH				
31 MIN		D INTERVALS	JSED FOR TIME	STOPWATCH (START	10"	24"	01/21/21 PT-01	4
Ancie			00:30:14	00:29:51	00:28:45	TIME			, , , , ,	
	· · · · · · · · · · · · · · · · · · ·					FINISH				
31 MIN)	D INTERVALS	JSED FOR TIME	STOPWATCH (START	10"	24"	03/05/21 PT-01	4
Anat	00:30:20	00:30:02	00:25:35	00:23:19	00:20:19	TIME				,
	y .					FINISH			0.4/0.0/0.4	
11 MIN		D INTERVALS	JSED FOR TIME	STOPWATCH (START	10"	24"	04/28/21 PT-02	5
		00:10:55	00:10:02	00:05:07	00:02:40	TIME				
						FINISH			00/05/04	
22 MIN	2	D INTERVALS	JSED FOR TIME	STOPWATCH (START	10"	24"	03/05/21 PT-02	5
***************************************	00:21:58	00:21:50	00:17:56	00:14:49	00:07:24	TIME				


DEEP TEST HOLE RESULTS

LOT#	TEST HOLE#	DATE	DEPTH	DESCRIPTION
1	TP-07	03/05/21	0" - 6" 6" - 32"	TOPSOIL TAN, SILTY LOAM ROCK @ 32"
1	TP-08	03/05/21	0" - 6" 6" - 42"	TOPSOIL TAN, SILTY LOAM ROCK @ 32"
2	TP-09	03/05/21	0" - 6" 6" - 44"	TOPSOIL TAN, SILTY LOAM GROUNDWATER @ 57"
2	TP-10	03/05/21	0" - 8" 8" - 32" 32" - 42"	TOPSOIL TAN, SILTY LOAM W/ COBBLE TAN, SILTY, CLAY LOAM GROUNDWATER @ 42"
3	TP-12	03/05/21	0" - 8" 8" - 38" 38" - 56"	TOPSOIL TAN, SILTY LOAM TAN, SILTY, CLAY LOAM GROUNDWATER @ 56"
3	TP-01	04/28/21	0" - 8" 8" - 56" 56" - 76"	TOPSOIL TAN, SILTY, SANDY LOAM TAN, SILTY, CLAY LOAM GROUNDWATER @ 72", ROCK @ 76"
4	TP-01	03/05/21	0" - 6" 6" - 44"	TOPSOIL TAN, SILTY, CLAY LOAM GROUNDWATER @ 42", ROCK @ 44"
4	TP-03	03/05/21	0" - 6" 6" - 41"	TOPSOIL TAN, SILTY, CLAY LOAM GROUNDWATER @ 40", ROCK @ 41"
5	TP-02	04/28/21	0" - 8" 8" - 48" 48" - 75"	TOPSOIL TAN, SILTY, SANDY LOAM BROWN, SILTY, SANDY, CLAY LOAM ROCK @ 75"
5	TP-05	03/05/21	0" - 8" 8" - 42" 42" - 67"	TOPSOIL TAN, SILTY LOAM TAN, SILTY, SANDY LOAM GROUNDWATER @ 67"

Z: \1051.11 - Newburgh Rte 32 Subdivision\Subdivision Plan.dwg Date Printed: May 06, 2021, 11:16am










12" (MIN) BUT AT LEAST 24"

1. SEPTIC TANK TO BE LOCATED A MINIMUM DISTANCE OF 10 FEET FROM THE BUILDING.
2. THERE SHALL BE NO REGRADING, IN THE AREA OF THE ABSORPTION FIELDS, EXCEPT AS SHOWN ON SWIMMING POOLS, DRIVEWAYS AND/OR STRUCTURES THAT MAY COMPACT THE SOIL ARE NOT TO BE CONSTRUCTED OVER ABSORPTION FIELDS. ASPHALTIC SEALS SHALL BE MAINTAINED BETWEEN THE SEPTIC TANK, AND ALL PIPES AND COVERS NO TRENCHES TO BE INSTALLED IN WET SOIL RAKE SIDES AND BOTTOM OF TRENCH PRIOR TO PLACING CHAMBERS IN ABSORPTION TRENCH. GROUT ALL PIPE PENETRATIONS INTO AND OUT OF ANY DISTRIBUTION OR DROP BOX. ALL CONSTRUCTION SHALL CONFORM TO THE REQUIREMENTS AS SET FORTH IN THE PUBLICATION "NEW YORK STATE DEPARTMENT OF HEALTH - RESIDENTIAL ONSITE WASTEWATER TREATMENT SYSTEMSS - DESIGN HANDBOOK, 2012 AND OCDOH DESIGN POLICY & STANDARDS - APPENDIX 75-A. ABSORPTION CHAMBER TO BE CAPPED AT ENDS. 10. PROVIDE A MINIMUM OF 30" OF SOLID PIPE PRIOR TO START OF LEACHING CHAMBERS AND BE BACKFILLED WITH NATIVE MATERIAL. 11. THERE MUST BE AN UNINTERRUPTED POSITIVE SLOPE FROM THE SEPTIC TANK (OR ANY PUMPING OR DOSING CHAMBER) TO THE BUILDING, ALLOWING SEPTIC GASES TO DISCHARGE THROUGH THE ACTUAL CONSTRUCTION. THERE SHALL BE NO UNNECESSARY MOVEMENT OF CONSTRUCTION EQUIPMENT IN THE ABSORPTION FIELD AREA BEFORE, DURING, OR AFTER CONSTRUCTION. EXTREME CARE MUST BE TAKEN DURING THE ACTUAL CONSTRUCTION SO TO AS TO AVOID ANY UNDUE COMPACTION THAT COULD RESULT IN A CHANGE OF ABSORPTION CAPACITY OF THE SOIL ON WHICH 13. THIS SYSTEM HAS NOT BEEN DESIGNED TO ACCOMMODATE GARBAGE GRINDERS, JACUZZI STYLE SPA TUBS OVER 100 GALLONS, OR WATER CONDITIONERS AND SHALL NOT BE INSTALLED WITHOUT ADDITIONAL REVIEW AND AND APPROVAL OF THE ORANGE COUNTY DEPARTMENT OF HEALTH.

ABSORPTION TILE FIELD OVERALL PLAN








SEPTIC TANK TO BE LOCATED A MINIMUM DISTANCE OF 10 FEET FROM THERE SHALL BE NO REGRADING, IN THE AREA OF THE ABSORPTION FIELDS, EXCEPT AS SHOWN ON THE APPROVED PLANS. SWIMMING POOLS, DRIVEWAYS AND/OR STRUCTURES THAT MAY COMPACT THE SOIL ARE NOT TO BE CONSTRUCTED OVER ABSORPTION 4. ASPHALTIC SEALS SHALL BE MAINTAINED BETWEEN THE SEPTIC TANK, AND ALL PIPES AND COVERS. NO TRENCHES TO BE INSTALLED IN WET SOIL. 6. RAKE SIDES AND BOTTOM OF TRENCH PRIOR TO PLACING CHAMBERS IN ABSORPTION TRENCH. 7. GROUT ALL PIPE PENETRATIONS INTO AND OUT OF ANY DISTRIBUTION 8. ALL CONSTRUCTION SHALL CONFORM TO THE REQUIREMENTS AS SET FORTH IN THE PUBLICATION "NEW YORK STATE DEPARTMENT OF HEALTH - RESIDENTIAL ONSITE WASTEWATER TREATMENT SYSTEMSS -DESIGN HANDBOOK, 2012 AND OCDOH DESIGN POLICY & STANDARDS -APPENDIX 75-A. ABSORPTION CHAMBER TO BE CAPPED AT ENDS. 10. PROVIDE A MINIMUM OF 30" OF SOLID PIPE PRIOR TO START OF LEACHING CHAMBERS AND BE BACKFILLED WITH NATIVE MATERIAL. 11. THERE MUST BE AN UNINTERRUPTED POSITIVE SLOPE FROM THE SEPTIC TANK (OR ANY PUMPING OR DOSING CHAMBER) TO THE BUILDING, ALLOWING SEPTIC GASES TO DISCHARGE THROUGH THE STACK VENT. 12. HEAVY EQUIPMENT SHALL BE KEPT OFF THE AREA OF THE ABSORPTION FIELDS EXCEPT DURING THE ACTUAL CONSTRUCTION. THERE SHALL BE NO UNNECESSARY MOVEMENT OF CONSTRUCTION EQUIPMENT IN THE ABSORPTION FIELD AREA BEFORE, DURING, OR AFTER CONSTRUCTION EXTREME CARE MUST BE TAKEN DURING THE ACTUAL CONSTRUCTION SO TO AS TO AVOID ANY UNDUE COMPACTION THAT COULD RESULT IN A CHANGE OF ABSORPTION CAPACITY OF THE SOIL ON WHICH THE DESIGN WAS BASED 13. THIS SYSTEM HAS NOT BEEN DESIGNED TO ACCOMMODATE GARBAGE GRINDERS, JACUZZI STYLE SPA TUBS OVER 100 GALLONS, OR WATER CONDITIONERS AND SHALL NOT BE INSTALLED WITHOUT ADDITIONAL REVIEW AND AND APPROVAL OF THE ORANGE COUNTY DEPARTMENT OF

FINISHED GRADE 45° BEND PROPOSED 4" PVC

TYPICAL CLEANOUT



CURTAIN DRAIN

No. DATE DESCRIPTION

INITIAL SUBMISSION

DRAWING STATUS

THE PLAN SET ISSUED FOR

OCDOH REALTY SUBDIVISION APPROVAL

OCDOH WATERMAIN EXTENSION APPROVAL

THIS PLAN SET HAS BEEN ISSUED SPECIFICALLY FOR THE APPROVAL OR ACTION NOTED ABOVE AND SHALL NOT BE USED

THIS SHEET SHALL BE CONSIDERED INVALID UNLESS

✓ PLANNING BOARD APPROVAL

FOR BID

FOR CONSTRUCTION

FOR ANY OTHER PURPOSE.

COPIES OF THIS DOCUMENT

WITHOUT AN ACTUAL OR

RED OR BLUE INK SHALL BE

ENGINEER'S SIGNATURE AND AN ORIGINAL STAMP

CONSIDERED INVALID.

FACSIMILE OF THE

UNAUTHORIZED

ALTERATIONS OR

ADDITIONS TO THIS

SEAL OF A LICENSED

IS A VIOLATION OF

DOCUMENT BEARING THE

PROFESSIONAL ENGINEER

SECTION 7209 SUBSECTION

1 - 05/07/21

2 OF THE NEW YORK STATE

REVISED PER PB ENGINEER COMMENTS 04/09/21

NUMBER

3 OF 4

N/A OF N/A


N/A OF N/A

N/A OF N/A

N/A OF N/A

ROSS WINGLOVITZ, P.E.

SHALLOW ABSORPTION TILE FIELD OVERALL PLAN





1. WELL IS TO BE CASED AND GROUTED FOR A MIN OF 50' IN LENGTH. CASING SHALL EXTEND MINIMUM 20" INTO BEDROCK. OVERSIZE DRILL HOLE (FOR GROUTING) TO BE 10" DIAMETER. EXPECTED DEPTH OF LOAM AND SHALE OVERBURDEN = 5 - 30 FEET EXPECTED DEPTH OF WATER BEARING FORMATION = 300 - 600 FEET THE WELL CASING TO CONFORM TO AWWA STANDARD A100 (LATEST EDITION). SANITARY WELL SEAL SHALL BE MONITOR MODEL NO 6WE-1, MFG BY THE BAKER MFG CO; EVANSVIILE, WIS., OR APPROVED EQUAL AND SHALL HAVE THE APPROVAL OF THE WATER 8. PITLESS ADAPTOR SHALL BE MONITOR MODEL NO 8PL61U, MFG BY THE BAKER MFG CO; EVANSVIILE, WIS., OR APPROVED EQUAL AND SHALL HAVE THE APPROVAL OF THE WATER 9. DISCHARGE PIPE: 1" MIN OF TYPE "K" COPPER WATER LINE. 10. WATER SERVICE LINES UNDER PRESSURE SHALL NOT PASS CLOSER THAN 10' OF A SEPTIC TANK, TILE FIELD, OR ANY OTHER PART OF A SEWAGE DISPOSAL SYSTEM. 11. PVC PIPE WITH O-RING JOINTS ARE REQUIRED FOR SEWAGE LINES BETWEEN 25 AND 50 FEET OF 12. MIN. WELL YIELD TO BE A MINIMUM OF 2 GAL PER MINUTE. ANY WELL PRODUCING BETWEEN 2-5 GPM REQUIRES 24 HOURS OF STORAGE WITHIN HOME. 13. CEMENT GROUT SHALL BE A MIXTURE OF 1 BAG CEMENT (94 LBS) AND 5 1/2 GAL OF CLEAN 14. ELECTRICAL WORK SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE REQUIREMENTS OF THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE. 15. CONSTRUCTION SHALL CONFORM TO THE REQUIREMENTS AS SET FORTH IN THE PUBLICATION

MINIMUM SEPARATION DISTANCES ARE MET. TYPICAL DRILLED WELL SECTION
SCALE: N.T.S.


16. WELLS ARE TO BE INSTALLED IN THE LOCATIONS SHOWN ON THE PLAN TO ASSURE THE

"RURAL WATER SUPPLY", NYS DEPT OF HEALTH, LATEST EDITION.





1250 GALLON SEPTIC TANK



PROVIDE WATERTIGHT JOINTS AT ALL INLET/OUTLET PIPES OUTLET TO NEXT DROP DISTRIBUTION BOX TO CONCRETE SLOPE 1"/FT ALONG COVER \ PER ASTM 2729 PIPE RUN . 4" SOLID PVC PER ASTM 2729 12" MIN SAND OR PEA GRAVEL

1. DROP BOX AS MANUFACTURED BY WOODARD'S CONCRETE PRODUCTS, INC. CATALOG No. DB-6DB OR APPROVED EQUAL


- 2. MINIMUM CONCRETE STRENGTH 4,000 PSI AT 28 DAYS
- 3. CONCRETE TO BE FIBER REINFORCED PER MANUFACTURER'S SPECIFICATION 4. SEAL ALL JOINTS AT INLET/OUTLET PIPES ASPHALTIC MATERIAL OR EQUIVALENT
- 5. PROVIDE SPEED LEVELERS AT ALL DISTRIBUTION BOX OUTLETS 6. UNUSED OUTLETS TO REMAIN PLUGGED
- 7. DISTRIBUTION BOXES SHOULD BE INSPECTED PERIODICALLY TO ASSURE THAT THEY ARE LEVEL AND OPERATING PROPERLY. 6 HOLE DROP DISTRIBUTION BOX



Wait The Required Time Confirm Utility Response Respect The Marks Dig With Care 800-962-7962

www.digsafelynewyork.com


	ORIGINAL	L SCALE IN INCHES						
		·						
7 ₀	ROPERTI Achieving Successful Rowith Innovative Design	TG 71 CLINTON STREE MONTGOMERY, NY 1254	T 49 27					
	SEPTIC DE	ESIGN DETAILS						
	HANOVER ROUTE 32 SUBDIVISION NYS ROUTE 32 TOWN OF NEWBURGH ORANGE COUNTY, NEW YORK							
	JOB #: DRAWN 1051.11	BY: RMB						
	DATE: SCALE: 04/05/21	AS NOTED C-300)					




NOTES:

- 1. STONE SIZE USE 2" STONE MIN, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT. 2. WIDTH - 10 FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH OF DRIVEWAY AT POINTS WHERE
- 3. SURFACE WATER ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL A MOUNTABLE BERM
- WITH 5:1 SLOPES WILL BE PERMITTED. 4. MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH SHALL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF- WAY. THIS MAY REQUIRED PERIODIC
- TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED, OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
- WASHING WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH
- STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE. 6. PERIODIC INSPECTIONS AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH SIGNIFICANT

STABILIZED CONSTRUCTION ENTRANCE




ITEM NUMBERS REFER TO NYSDOT SPECS. PAVEMENT TO EXTEND FROM CURB TO RIGHT OF WAY LINE. DRIVEWAY PAVEMENT SECTION



NOTES: 1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE. 2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 1:2. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED A WITH EITHER SILT FENCING OR STRAWBALES, THEN STABILIZED WITH VEGETATION OR


4. SEE SPECIFICATIONS (THIS MANUAL) FOR INSTALLATION OF SILT FENCE.

ORANGE CONSTRUCTION



CONSTRUCTION SPECIFICATIONS

- 1. ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS AND OTHER OBJECTIONABLE SHALL BE REMOVED AND DISPOSED OF SO AS NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE WATERWAY.
- 2. THE WATERWAY SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE AND CROSS SECTION AS REQUIRED TO MEET THE CRITERIA SPECIFIED HEREIN, AND BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH WILL IMPEDE NORMAL
- 3. ALL EARTH REMOVED AND NOT NEEDED IN CONSTRUCTION SHALL BE SPREAD OR DISPOSED OF SO THAT IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE
- 4. FILL SHALL BE COMPACTED AS NEEDED IN CONSTRUCTION TO PREVENT UNEQUAL SETTLEMENT THAT WOULD CAUSE DAMAGE IN THE COMPLETED WATERWAY. 5. WATERWAY SHALL BE SEEDED AND STABILIZED JUTE OR EXCELSIOR MATTING UNTIL THE VEGETATION IS ESTABLISHED.




STABILIZATION OF ALL AREAS WITHIN 125 FEET OF FENCING.

ALL ORANGE CONSTRUCTION FENCING SHALL BE MAINTAINED THROUGHOUT

THE ORANGE CONSTRUCTION FENCING WILL BE REMOVED UPON FINAL

TREES AND STONE WALLS ARE TO BE PRESERVED.

CONSTRUCTION TO PROTECT SENSITIVE AREAS.



SCALE: N.T.S.

EROSION AND SEDIMENTATION CONTROL NOTES

REMOVAL REQUIRED FOR CONSTRUCTION. SEDIMENT BASIN, TEMPORARY DIVERSION SWALE DRAINAGE STRUCTURES, AND RIP-RAP

1. SITE DISTURBANCE SHALL BE LIMITED TO THE MINIMUM NECESSARY GRADING AND VEGETATION

2. TEMPORARY EROSION CONTROL MEASURES, INCLUDING SILT FENCES AND/OR STRAW BALE DIKES, PROTECTION SHALL BE INSTALLED PRIOR TO GROUND DISTURBANCE FOR GRADING AND

3. ALL DISTURBED AREAS SHALL BE SEEDED AND MULCHED AS SOON AS PRACTICAL FOLLOWING DISTURBANCE TO STABILIZE BARE SOIL AND PROMOTE THE PROMPT RE-ESTABLISHMENT OF 3.1. AN ADEQUATE SEEDBED SHALL BE PREPARED BY SCARIFYING COMPACTED SOIL AND REMOVING SURFACE DEBRIS AND OBSTACLES.

3.2. LIME SHALL BE APPLIED SUFFICIENTLY TO ATTAIN A SOIL ACIDITY PH OF 6.0 TO 7.0. 3.3. FERTILIZER (5-10-10 MIXTURE OR EQUIVALENT) SHALL BE APPLIED PER SOIL TEST RESULTS OR AT A RATE OF 600 LBS. PER ACRE. 3.4. DISTURBED AREAS WHICH WILL REMAIN TEMPORARILY FALLOW FOR PERIODS GREATER THAN 30 DAYS SHALL BE SEEDED AT THE FOLLOWING RATE TO PRODUCE TEMPORARY GROUND COVER:

30 LBS. RYEGRASS (ANNUAL OR PERENNIAL) PER ACRE. DURING THE WINTER, USE 100 LBS. CERTIFIED "AROOSTOOK" WINTER RYE (CEREAL RYE) PER ACRE. 3.5. PERMANENT SEEDING SHALL BE APPLIED ON 4" MIN TOPSOIL AT THE FOLLOWING RATE: 8 LBS EMPIRE BIRDSFOOT TREFOIL OR COMMON WHITE CLOVER PER ACRE PLUS 20 LBS TALL FESCUE PER ACRE PLUS 2 LBS REDTOP OR 5 LBS RYEGRASS (PERENNIAL) PER ACRE

3.6. ALL SEEDING SHALL BE PERFORMED USING THE BROADCAST METHOD OR HYDROSEEDING, UNLESS OTHERWISE APPROVED. 3.7. ALL DISTURBED AREAS SHALL BE STABILIZED SUBSEQUENT TO SEEDING BY APPLYING 2 TONS OF STRAW MULCH PER ACRE. STRAW MULCH SHALL BE ANCHORED BY APPLYING 750 LBS OF WOOD FIBER MULCH PER ACRE WITH A HYDROSEEDER, OR TUCKING THE MULCH WITH SMOOTH DISCS OR OTHER MULCH ANCHORING TOOLS TO A DEPTH OF 3". MULCH ANCHORING TOOLS SHALL BE PULLED ACROSS SLOPES ALONG TOPOGRAPHIC CONTOURS.

4. ALL EROSION AND SEDIMENTATION CONTROL MEASURES AND DRAINAGE STRUCTURES SHALL BE INSPECTED FOLLOWING EVERY RAIN EVENT, AND MAINTENANCE AND REPAIRS SHALL BE PERFORMED PROMPTLY TO MAINTAIN PROPER FUNCTION. TRAPPED SEDIMENT SHALL BE REMOVED AND DEPOSITED IN A PROTECTED AREA IN A PROPER MANNER WHICH WILL NOT RESULT IN EROSION.

PERMANENTLY STABILIZED AND GROUND COVER IS COMPLETELY REESTABLISHED. FOLLOWING STABILIZATION, TEMPORARY MEASURES SHALL BE REMOVED TO AVOID INTERFERENCE WITH 6. ALL STORM INLETS TO BE PROTECTED FROM SEDIMENTATION DURING CONSTRUCTION.

TEMPORARY CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL DISTURBED AREAS ARE

7. SYNTHETIC OR ORGANIC SOIL STABILIZERS MAY BE USED UNDER SUITABLE CONDITIONS AND IN SUFFICIENT QUANTITIES.


8. MULCH NETTING SUCH AS PAPER, JUTE, EXCELSIOR, COTTON OR PLASTIC MAY BE USED. STAPLE IN PLACE. OVER HAY OR STRAW MULCH. USE A DEGRADABLE NETTING IN AREAS TO BE MOWED. 9. STABILIZATION OF STEEP SLOPES SHALL BE ACHIEVED BY APPLYING LIME AND FERTILIZER AS SPECIFIED ABOVE AND SEEDING WITH THE FOLLOWING MIXTURE: MATERIAL PERENNIAL RYE GRASS

SPREADING FESCUE 10. OPTIMUM SEEDING PERIODS ARE 3/15-6/1 AND 8/1-10/15.

CROWN VETCH

11. ALL UPSTREAM SITE WORK AND STABILIZATION SHALL OCCUR BEFORE CONNECTING UNDERGROUND DETENTION/INFILTRATION FACILITY TO PREVENT ANY ERODED SEDIMENTS FROM ENTERING UNDERGROUND FACILITY.

12. IN ACCORDANCE WITH THE NYSDEC SPDES GP 0-20-001, THERE SHALL BE NO MORE THAN 5 ACRES DISTURBED AT ANYONE TIME.



EFFLUENT ALONG THE SURFACE FOR INFILTRATION. 2. CONNECTION OF ROOF LEADERS TO CLOSED SYSTEMS IS PROHIBITED. HOMEOWNERS SHALL MAINTAIN SPLASH BLOCK LAWN AREA AS SHOWN ON THE PLANS TO PROVIDE INFILTRATION OF STORMWATER ROOF RUNOFF.

EARTHWORK CONSTRUCTION NOTES

1. ALL WORK TO BE PERFORMED TO THE SPECIFICATIONS OF THE TOWN OF NEWBURGH.

- 2. ALL TOPSOIL, ROOTS, STUMPS AND OTHER DELETERIOUS MATERIAL SHALL BE REMOVED FROM ALL CONSTRUCTION AREAS.
- 3. ALL FILL FOR POND CONSTRUCTION, BELOW BUILDINGS AND PAVEMENT TO BE COMPACTED TO 95% OF MAXIMUM DRY DENSITY AS DETERMINED BY MODIFIED PROCTOR COMPACTION TEST ASTM D1557. 4. CELLAR, ROOF AND FOOTING DRAINS SHALL CONNECT TO THE STORM DRAINAGE SYSTEM OR OTHER FREE-FLOWING OUTLET AT A MINIMUM SLOPE OF 0.5%. FOOTING DRAIN SHALL BE INSTALLED BENEATH BOTTOM OF FOOTING.
- 5. COMPLETION OF GRADING AND BASIN, BERMS AFTER OCTOBER 15 SHALL REQUIRE MULCHING AND ANCHORING IN ACCORDANCE WITH NOTES ENTITLED "SEDIMENTATION EROSION CONTROL".
- 6. ALL SLOPES IN EXCESS OF 3H:1V SHALL BE CONSTRUCTED WITH LOCALLY AVAILABLE GLACIAL TILL. THE EMBANKMENT FILL SHALL BE PLACED IN SIX-INCHTHICK LIFTS. EACH LIFT SHALL BE PLACED AND COMPACTED TO 95% OF MAXIMUM DRY DENSITY AS DETERMINED BY MODIFIED PROCTOR COMPACTION TEST ASTM D1557.
- CONSTRUCT POND EMBANKMENT WITH LOCALLY AVAILABLE GLACIAL TILL WITH 3H:1V SIDE SLOPES OR AS NOTED ON PLAN. THE EMBANKMENT FILL SHALL BE PLACED IN A SIX-INCH THICK CONTINUOUS LAYER OVER THE ENTIRE LENGTH.EACH LIFT SHALL BE PLACED AT OPTIMUM MOISTURE CONTENT AND COMPACTED TO

95% OF MAXIMUM DRY DENSITY AS DETERMINED BY MODIFIED PROCTOR COMPACTION TEST ASTM D1557.

- 8. STABILIZATION OF POND BERMS, AND ALL SLOPES IN EXCESS OF 3H:1V IN ACCORDANCE WITH "EROSION AND
- SEDIMENTATION CONTROL NOTES". 9. ALL POND OUTLETS SHALL HAVE SEEPAGE CONTROL COLLARS PLACED AT 1/3 AND 2/3 THE WIDTH OF THE
- 10. SOIL RESTORATION SHALL BE APPLIED TO ALL DISTURBED AREAS THAT WILL REMAIN AS PERVIOUS SURFACES. SOIL RESTORATION SHALL CONSIST OF THE FOLLOWING:
- 10.A. APPLY 3 INCHES OF COMPOST OVER SUBSOIL 10.B. TILL COMPOST INTO SUBSOIL TO A DEPTH OF AT LEAST 12 INCHES USING A CAT-MOUNTED RIPPER,
- TRACTOR MOUNTED DISC, OR TILLER, MIXING, AND CIRCULATING AIR AND COMPOST INTO SUB-SOILS. 10.C. ROCK-PICK UNTIL UPLIFTED STONE/ROCK MATERIALS OF FOUR INCHES AND LARGER SIZE ARE CLEANED
- OFF THE SITE. 10.D. APPLY TOPSOIL TO A DEPTH OF 6 INCHES.

SEQUENCE OF CONSTRUCTION ACTIVITY

- 1. PRE-CONSTRUCTION: NOTIFY APPROPRIATE MUNICIPAL AND UTILITY OFFICIALS 3 DAYS PRIOR TO START OF CONSTRUCTION. CONSTRUCTION STAGING: STAKE OUT LIMIT OF DISTURBANCE. INSTALL SILT FENCE DOWNHILL OF PROPOSED CONSTRUCTION. INSTALL ORANGE CONSTRUCTION FENCING ALONG THE LIMITS OF DISTURBANCE. INSTALL STABILIZED CONSTRUCTION ENTRANCE(S). INSTALL PERMANENT / TEMPORARY
- GRASSED SWALES. 3. CLEARING AND GRUBBING: REMOVE VEGETATION FROM AREA OF CONSTRUCTION. STRIP TOPSOIL AND STOCKPILE IN AREAS SHOWN ON THE PLAN. INSTALL SEDIMENT SEDIMENT BARRIERS AROUND AND ESTABLISH

ESTABLISH TEMPORARY STABLIZATION ON AREAS THAT WILL BE GRADED AGAIN


- TEMPORARY VEGETATION ON TOPSOIL STOCKPILES. 4. ROUGH GRADING: CUT AND FILL SITE TO APPROXIMATE ELEVATIONS SHOWN ON THE PLAN. IMPLEMENT DUST CONTROL MEASURES AS NECESSARY. ESTABLISH PERMANENT STABLIZATION IN AREAS THAT ARE COMPLETE.
- MORE THAN 21 DAYS FROM LAST DISTURBANCE. 5. DRIVEWAY / BUILDING CONSTRUCTION AND UTILITY INSTALLATION: FINAL GRADING AND CONSTRUCTION OF DRIVEWAYS. BUILDING EXCAVATION AND
- CONSTRUCTION. INSTALL UTILITIES. ENSURE ALL EROSION CONTROL MEASURES ARE IN WORKING ORDER 6. FINAL GRADING AND LANDSCAPING: COMPLETE FINE GRADING OF SITE. SPREAD TOPSOIL AND PREPARE FOR PERMANENT SEEDING AND PLANTING. ESTABLISH
- ALL SITE LANDSCAPING AND PLANTINGS 7. POST CONSTRUCTION: UPON STABILIZATION OF THE SITE AND ESTABLISHMENT OF ALL VEGETATION COVER, REMOVE ALL REMAINING TEMPORARY EROSION CONTROL MEASURES SUCH AS SILT FENCE. REMOVE ALL SILT AND DEBRIS

PERMANENT VEGETATION IN ALL REMAINING UNSTABILIZED AREAS. INSTALL


FROM THE SITE INCLUDING ROADWAYS, CATCH BASINS AND STORM DRAINS.


No. DATE DESCRIPTION INITIAL SUBMISSION REVISED PER PB ENGINEER COMMENTS 04/09/21

1	DRAWING STATUS	ISSUE DATE:							
	DRAWING STATUS	05	/07/	/21					
1	THIS SHEET IS PART OF	SHEET							
L	THE PLAN SET ISSUED FOR	NU	JMB	ER					
	CONCEPT APPROVAL	N/A	OF	N/A					
	☑ PLANNING BOARD APPROVAL	4	OF	4					
	OCDOH REALTY SUBDIVISION APPROVAL	N/A	OF	N/A					
I	OCDOH WATERMAIN EXTENSION APPROVAL	N/A	OF	N/A					
ſ	☐NYSDEC APPROVAL	N/A	OF	N/A					
	□NYSDOT APPROVAL	N/A	OF	N/A					
	☐ OTHER	N/A	OF	N/A					
	☐FOR BID	N/A	OF	N/A					
	FOR CONSTRUCTION	N/A	OF	N/A					
	THIS PLAN SET HAS BEEN ISSUED SPECIFICALLY FOR THE APPROVAL OR ACTION NOTED ABOVE AND SHALL NOT BE USED FOR ANY OTHER PURPOSE. THIS SHEET SHALL BE CONSIDERED INVALID UNLESS ACCOMPANIED BY ALL SHEETS OF THE DENOTED PLAN SET(S).								









ORANGE COUNTY, NEW YORK AS NOTED C-30 1 - 05/07/21

* Aeration includes the use of machines such as tractor-drawn implements with coulters making a narrow slit in the soil, a roller with many spikes making indentations in the soil, or prongs which function like a mini-subsoiler. ** Per "Deep Ripping and De-compation, DEC 2008".

SOIL RESTORATION NOTES

HSG C&D

inches of topsoil

HSG C & D

apply 6 inches | Aerate* and apply 6

Apply full Soil Restoration (de-

Restoration not required, but may be

applied to enhance the reduction

Soil Restoration is required on

redevelopment projects in areas

where existing impervious area will be converted to pervious area.

specified for appropriate practices.

compaction and compost

Comments/Examples

Preservation of Natural Features

Protect area from any ongoing

Keep construction equipment from

rossing these areas. To protect

newly installed practice from any

ongoing construction activities

fence area

construct a single phase operation

Clearing and grubbing

construction activities.

Type of Soil Disturbance | Soil Restoration Requirement

HSG A &B

of topsoil

HSG A &B

Aerate and

apply 6 inches of topsoil

Minimal soil disturbance Restoration not required

Restoration not permitted

No soil disturbance

Areas where topsoil is

Areas of cut or fill

stripped only - no change

Heavy traffic areas on site (especially in a zone 5-25

feet around buildings but

not within a 5 foot

perimeter around

foundation walls)

Areas where Runoff

Infiltration practices are

Redevelopment projects

Reduction and/or